

Lockyer Valley Regional Council

26 Railway Street, PO Box 82, Gatton Qld 4343
All official correspondence to be addressed to the CEO
Telephone 1300 005 872 | Facsimile (07) 5462 3269
Email mailbox@lvrc.qld.gov.au | www.lockyervalley.qld.gov.au

DECISION NOTICE

Planning Act 2016

Application ID: OW2024/0019
Enquiries: Scott Hambleton
Contact: 5462 0618

29 July 2024

Park Lake Adare Pty Ltd TTE
Park Lake Adare Unit Trust
C/- Van Der Meer Consulting
Level 3, 51 Alfred Street
FORTITUDE VALLEY QLD 4006

Attention: Chris Liao

Dear Chris

DEVELOPMENT PERMIT FOR OPERATIONAL WORKS FOR ROADWORK, STORMWATER AND EARTHWORKS (RL2022/0017.03 – STAGES 4 AND 5)

I wish to advise that on 26 July 2024, the application described below was approved subject to conditions.

Application Details

Description of Development: Development Permit for Operational Works for Roadwork,

Stormwater and Earthworks (RL2022/0017.03 – Stages 4 and 5)

Street Address: 63 Redbank Creek Road, Adare

Real Property Description: L900 SP328401

Conditions of Approval

The conditions of approval are attached.

Unless otherwise specified, all assessment manager conditions of this development approval relating to the provision of infrastructure are non-trunk infrastructure conditions for Chapter 4 of the *Planning Act 2016*.

Currency Period

The currency period for this Development Permit is two (2) years starting the day this Development Permit takes effect (refer to Section 85 of the *Planning Act 2016*). The Approval will lapse unless the works are substantially started within the currency period.

Representations and Rights of Appeal

You are entitled to appeal this decision or make representations in relation to the conditions of approval.

Within your appeal period (i.e. 20 business days after the Decision Notice is given), you may suspend your appeal period and make written representations to Council about the conditions of approval. If Council agrees with any of the representations, a Negotiated Decision Notice will be given. Only one Negotiated Decision Notice may be given. If a Negotiated Decision Notice is given, your 20 business day appeal period will commence again.

The rights of applicants to appeal to a tribunal or the Planning and Environment Court against decisions about development applications are set out in chapter 6, part 1 of the *Planning Act 2016*. Attached is an extract from the *Planning Act 2016* which details your appeal rights.

Commencement of Approval

This approval takes effect in accordance with section 71 of the *Planning Act 2016*.

Yours faithfully

Michael Dargusch

COORDINATOR DEVELOPMENT ASSESSMENT

Attach: Schedule 1 – Lockyer Valley Regional Council's conditions of approval and advisory notes

Approved Plans/Documents

Appeal Rights (extracts from the Planning Act 2016)

CC: Urban Utilities

Development@urbanutilities.com.au

Schedule 1 – Lockyer Valley Regional Council's Conditions of Approval and Advisory Notes

APPROVED PLANS

Plan No.	Rev.	Plan Name	Date
C4000	Α	COVER SHEET	15/4/24
C4001	В	STANDARD NOTES	26/6/24
C4002	Α	SITE PLAN – SHEET 1	15/4/24
C4003	Α	SITE PLAN – SHEET 2	15/4/24
C4004	Α	SITE PLAN – SHEET 3	15/4/24
C4100	В	EROSION AND SEDIMENT CONTROL PLAN - SHEET 1	26/6/24
C4101	В	EROSION AND SEDIMENT CONTROL PLAN - SHEET 2	26/6/24
C4102	D	EROSION AND SEDIMENT CONTROL PLAN - SHEET 3	26/6/24
C4190	Α	EROSION AND SEDIMENT CONTROL DETAILS	15/4/24
C4191	Α	EROSION AND SEDIMENT CONTROL NOTES	15/4/24
C4200	С	BULK EARTHWORKS SECTION SHEET 1	26/6/24
C4201	В	BULK EARTHWORKS SECTION SHEET 2	26/6/24
C4202	В	BULK EARTHWORKS SECTION SHEET 3	26/6/24
C4290	С	BULK EARTHWORKS DETAILS	10/7/24
C4300	Α	PAVEMENT PLAN - SHEET 1	15/4/24
C4301	Α	PAVEMENT PLAN - SHEET 2	15/4/24
C4302	С	PAVEMENT PLAN - SHEET 3	06/6/24
C4400	Α	ROADWORKS PLAN - SHEET 1	15/4/24
C4401	Α	ROADWORKS PLAN - SHEET 2	15/4/24
C4402	С	ROADWORKS PLAN - SHEET 3	06/6/24
C4430	Α	SIGNS AND PAVEMENT MARKING PLAN - SHEET 1	15/4/24
C4431	Α	SIGNS AND PAVEMENT MARKING PLAN - SHEET 2	15/4/24
C4432	Α	SIGNS AND PAVEMENT MARKING PLAN - SHEET 3	15/4/24
C4450	Α	ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET 1	15/4/24
C4451	Α	ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET 2	15/4/24
C4452	Α	ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET 3	15/4/24
C4453	Α	ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET 4	15/4/24
C4454	Α	ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 1	15/4/24
C4455	Α	ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 2	15/4/24
C4456	Α	ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 3	15/4/24
C4457	Α	ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 4	15/4/24
C4458	Α	ROAD LONGITUDINAL SECTION - BURTON CRESCENT - SHEET 1	15/4/24
C4459	Α	ROAD LONGITUDINAL SECTION - BURTON CRESCENT - SHEET 2	15/4/24
C4460	С	ROAD CROSS SECTIONS - BURTON CRESCENT - SHEET 1	26/6/24

C4461	С	ROAD CROSS SECTIONS - BURTON CRESCENT - SHEET 2	26/6/24
C4462	В	ROAD CROSS SECTIONS - BURTON CRESCENT - SHEET 3	26/6/24
C4480	С	INTERSECTION DETAILS	26/6/24
C4490	В	ROADWORKS DETAILS	26/6/24
C4500	С	DRAIANGE CATCHMENT PLAN	06/6/24
C4501	В	DRAINAGE PLAN - SHEET 1	09/5/24
C4502	В	DRAINAGE PLAN - SHEET 2	09/5/24
C4503	D	DRAINAGE PLAN - SHEET 3	06/6/24
C4510	Α	DRAINAGE BIO RETENTION BASIN DETAILS	15/4/24
C4550	В	DRAINAGE LONGITUDINAL SECTIONS - SHEET 1	09/5/24
C4551	Α	DRAINAGE LONGITUDINAL SECTIONS - SHEET 2	15/4/24
C4560	Α	DRAINAGE CALCULATIONS	15/4/24
C4700	Α	BUSHFIRE TRAIL 3 AND 4 PLAN	15/4/24
C4701	Α	BUSHFIRE TRAIL 3 LONGITUDINAL SECTION - SHEET 1	15/4/24
C4702	Α	BUSHFIRE TRAIL 3 LONGITUDINAL SECTION - SHEET 2	15/4/24
C4703	Α	BUSHFIRE TRAIL 3 LONGITUDINAL SECTION - SHEET 3	15/4/24
C4704	Α	BUSHFIRE TRAIL 3 CROSS SECTIONS - SHEET 1	15/4/24
C4705	Α	BUSHFIRE TRAIL 3 CROSS SECTIONS - SHEET 2	15/4/24
C4706	Α	BUSHFIRE TRAIL 3 CROSS SECTIONS - SHEET 3	15/4/24
C4707	Α	BUSHFIRE TRAIL 4 LONGITUDINAL AND CROSS SECTIONS	15/4/24
C4708	Α	BUSHFIRE TRAIL 5 AND 6 PLAN	15/4/24
C4709	Α	BUSHFIRE TRAIL 5 LONGITUDINAL SECTION - SHEET 1	15/4/24
C4710	Α	BUSHFIRE TRAIL 5 LONGITUDINAL SECTION - SHEET 2	15/4/24
C4711	Α	BUSHFIRE TRAIL 5 LONGITUDINAL SECTION - SHEET 3	15/4/24
C4712	Α	BUSHFIRE TRAIL 5 CROSS SECTIONS - SHEET 1	15/4/24
C4713	Α	BUSHFIRE TRAIL 5 CROSS SECTIONS - SHEET 2	15/4/24
C4714	Α	BUSHFIRE TRAIL 5 CROSS SECTIONS - SHEET 3	15/4/24
C4715	Α	BUSHFIRE TRAIL 6 LONGITUDINAL AND CROSS SECTIONS	15/4/24
C4716	Α	BUSHFIRE TRAIL DETAILS	15/4/24

ASSESSMENT MANAGER CONDITIONS

No.	Condition	Timing			
GENI	GENERAL				
1.	Undertake all approved works in accordance with the approved plans as listed within this decision notice and any works required by conditions of this approval at no cost to Council.	At all times.			
2.	A Works on a Road Reserve Permit must be obtained for any works involving closing of Council roads or working on or adjacent to existing roads or road reserves.	Prior to Pre- Start Meeting.			
	Advice Note: Refer to Council's <u>website</u> for information about how to apply.				
3.	Submit to Council for approval, test results for subgrade and final pavement designs certified by a RPEQ prior to construction of road pavements. Pavement Design to be in accordance with Austroads Guide to Pavement Technology Part 2: Pavement Structural Design or the Department of Transport and Main Roads design standards after stripping of topsoil and assessment of soaked sub-grade CBR values and using an ESA's or design traffic based on traffic engineering predictions.	Prior to commencement of road construction.			
	Advice Notes:				
	 A minimum five (5) business days' written notice must be provided to Council requesting approval for final pavement designs. Provide soil test results from the source quarry taken within two weeks of the pavement design date. 				
4.	Provide pavement thickness of no less than 300 mm for including a minimum of 30mm of AC surfacing. The total pavement thickness as determined from the design charts is not to include the thickness of AC surfacing which is deemed to be a wearing surface only unless the AC thickness is greater than 75mm".	At all times.			
5.	Install any new or reinstated signage in accordance with the IPWEAQ standard drawing no. RS 131. All new signage shall be coated with Class 1 retro-reflective material in accordance with AS1743: Road signs – Specifications.	At all times.			
BON	DS AND SECURITIES				
6.	Submit the following to Council: a. Priced Bill of Quantities prepared and certified by a Registered Professional Engineer Queensland (RPEQ) for the earthworks and stabilisation works. b. Erosion and Sediment Control (ESC) Bond equivalent to at least 3% of the value of the earthworks and stabilisation works or \$10,000 (whichever is greater). The ESC Bond is a security for the stabilisation of exposed areas where there are earthworks and the performance of restoration works, and for achieving grass coverage at the completion of works.	Prior to a prestart meeting.			

	T	
	Advice Note: The Erosion and Sediment Control (ESC) Bond will be	
_	released after the project is accepted off-maintenance.	5
7.	MAINTENANCE BOND – CIVIL WORKS	Prior to
	Submit the following to Council:	acceptance of
	a. Priced Bill of Quantities prepared and certified by a Registered	works On-
	Professional Engineer Queensland (RPEQ) for all development	Maintenance.
	works which are to be contributed to Council.	
	b. Maintenance Bond – Civil Works equivalent to at least 10% of the	
	value of the development works which are to be contributed to	
	Council or \$5,000 (whichever is greater). The Maintenance Bond	
	 Civil Works is a security to ensure the works are maintained 	
	during the maintenance period.	
	Advice Note: The Maintenance Bond – Civil Works will be released	
	after the project is accepted off-maintenance.	
PRF-	START MEETING REQUIREMENTS	
8.	Submit a written request for Council's delegated officers to attend a Pre-	Prior to
Ο.	Start Meeting for the proposed works with the Engineer (RPEQ) and	commencement
	Contractor. The written request must include at a minimum the following	of works.
	details:	OI WOINS.
	a. The Engineer (RPEQ), the Principal Contractor, including the name	
	and contact details during and outside of construction hours.	
	1	
	b. The supervising engineer's office and after hours contact details.	
	c. Date of commencement of works and expected duration	
	(programme of works).	
	d. Proposed haul route during construction works.	
	e. Pre- construction dilapidation report on existing Council	
	infrastructure for identified local section of the haul route during	
	construction works.	
	f. CCTV footage and an inspection report for underground	
	stormwater drainage works along with a letter from a suitably	
	qualified and experienced RPEQ stating that CCTV inspection	
	report and video had been reviewed and identifying any issues.	
	g. Proposed access locations for trucks and other heavy machinery	
	during construction phase.	
	h. Works on a Road Reserve Permit for traffic management and any	
	lane/footpath closures during construction (if required).	
	i. Erosion and sediment control plans.	
	j. A set of "Issued for Construction" drawings, amended if required	
	by the conditions of this approval.	
	k. Evidence of possession of site by contractor.	
	I. Public Liability Insurance to a limit of \$20,000,000 with a notation	
	with the Local Government as an Insured Party that is	
	current/valid for the full duration of works.	
	m. Workers' Compensation Insurance.	
	n. Evidence of Bond Payment(s) as per relevant conditions.	
	The Pre-Start Meeting date and time will be confirmed by Council's	
	delegated officer.	
	ELOPMENT WORKS	
9.	All works associated with this approval must occur within the following	At all times.
	times, unless otherwise approved in writing by the assessment manager:	

	Monday to Saturday (inclusive) - 6:30am to 6:30pm Sunday and Public Holidays - No work permitted	
10.	Carry out works to ensure compliance with Work Health and Safety legislative requirements.	At all times.
11.	Ensure all work sites are maintained in a clean, orderly state at all times.	At all times.
12.	Manage all waste in accordance with the relevant legislation and regulations and dispose of regulated waste at a licensed facility by a licensed regulated waste disposal contractor.	At all times.
13.	All services crossings for existing or completed new roads must be carried out only using under boring technique and open cut crossing will not be permitted.	At all times.
14.	Ensure the re-location and protection of any Council and public utility services infrastructure and assets that may be impacted on during construction of the development.	At all times.
15.	Repair all damages incurred to Council and public utility services infrastructure and assets to relevant authority's standards as a result of the proposed development, immediately should hazards exist for public health and safety or vehicular safety. Otherwise, repair all damage immediately upon completion of works associated with the development.	At all times.
16.	Ensure that development works on the subject land do not lead to ponding of stormwater or cause actionable nuisance to adjoining properties.	At all times.
17.	Protect nearby property owners from dust pollution arising from construction and maintenance of the works required by this approval in accordance with requirements of the <i>Environmental Protection Act 1994</i> .	At all times.
18.	In the event that bona fide complaints are received by Council in relation to dust emissions from the site or Council notices that a non-compliance exists, dust mitigation measures must be undertaken as directed by the Council.	At all times.
19.	Provide a minimum 100mm capping layer of good quality, non-dispersive soil on all areas disturbed during the earthworks.	Prior to acceptance on-maintenance.
20.	VERGES All verges are to be: a. Topsoiled to a depth of at least 100mm, using topsoil free of stones and deleterious matter, and lightly compacted. b. Provided with a continuous turf strip behind all new kerb and channel and any footpaths. c. Fully turfed or grassed.	Prior to acceptance of works On-Maintenance.
	Advice Note: Specifications are detailed in the <i>Lockyer Valley Planning Scheme</i> , Planning Scheme Policy 6 Infrastructure Design.	
21.	Disturbed areas on newly created lots and balance areas (excluding verges) must be seeded to achieve a minimum of 80% grass coverage, prior to on maintenance.	Prior to acceptance on-maintenance.
22.	Install signage displaying the business and afterhours telephone number/s of the applicant, supervising engineer and Principal Contractor as well as the operational works application number.	At all times.

23.	Ensure that supervision of all construction works is carried out by a suitably qualified and experienced Engineer (RPEQ).	At all times.
24.	Allow Council to enter a work site to which this approval relates and	At all times.
	undertake testing or analysis of any part of the construction, and Council	
	is not liable for the rectification of or compensation for any damage	
	caused in the testing or analysis process. Should work be found to be not	
	constructed to specification or of poor quality, rectification works must	
	be undertaken by the Principal Contractor.	
EPOS	SION AND SEDIMENT CONTROL	
25.	Implement erosion and sediment control generally in accordance with	At all times.
25.	the approved drawings and the Best Practice Erosion and Sediment	At all tilles.
	• • • • • • • • • • • • • • • • • • • •	
	Control guidelines by the International Erosion Control Association	
	Australasia. Where the drawings and the guidelines are conflicting, the	
26	requirements of the guidelines take precedence.	A
26.	The supervising engineer must undertake inspections of the erosion and	At all times.
	sediment control devices after all significant rain events. Where	
	necessary, the devices will be modified, repaired or improved to prevent	
	any erosion or sediment discharge from the development in future rain	
	events.	
27.	Implement and maintain measures to prevent the tracking of sediment	At all times
	to and from the site onto the adjoining street network for the duration	during
	of the construction period. Any sediment discharging from the site to the	construction.
	road network must be cleaned immediately at the expense of the	
	developer.	
STOC	KPILING	
28.	All temporary stockpiles of erodible material must be:	At all times.
	a. Protected from wind, rain, concentrated surface flow, and	
	excessive up-slope stormwater surface flows; and	
	b. Located up-slope of an appropriate sediment control system; and	
	c. Provided with an appropriate protective cover (synthetic or	
	organic) if the materials are likely to be stockpiled for more than	
	four (4) weeks; or	
	d. Provided with an appropriate protective cover (synthetic or	
	organic) if the materials are likely to be stockpiled for more than	
	ten (10) days during months of high erosion risk; or	
	e. Provided with an appropriate protective cover (synthetic or	
	organic) if the materials are likely to be stockpiled for more than	
	five (5) days during months of extreme erosion risk.	
IMPO	ORT OR EXPORT OF MATERIALS	
29.	This approval does not extend to any material proposed to be imported	At all times.
	This approval does not extend to any material proposed to be imported [
	to or exported from the site other than:	, , , , , , , , , , , , , , , , , , ,
	, , , , , , , , , , , , , , , , , , , ,	, , , , , , , , , , , , , , , , , , , ,
	to or exported from the site other than:	
	to or exported from the site other than: a. from or to site(s) that have a current Development Approval	
	to or exported from the site other than: a. from or to site(s) that have a current Development Approval enabling them to export/accept any material; or	
30.	to or exported from the site other than: a. from or to site(s) that have a current Development Approval enabling them to export/accept any material; or b. the material is being exported to and accepted at a licensed Council refuse facility.	Prior to
30.	to or exported from the site other than: a. from or to site(s) that have a current Development Approval enabling them to export/accept any material; or b. the material is being exported to and accepted at a licensed Council refuse facility. Submit to Council, the following for approval in the event it is proposed	
30.	to or exported from the site other than: a. from or to site(s) that have a current Development Approval enabling them to export/accept any material; or b. the material is being exported to and accepted at a licensed Council refuse facility.	Prior to

- a. details of the location of any material to be sourced for fill including the volume of fill to be moved from any particular source site:
- details of the final location for any material to be exported from the site from excavations including the volume to be moved to any particular site;
- c. the proposed haulage route(s) and truck sizes for carting of the material; and
- d. Council approval will be required for all roads on the haul route below Collector standard.

Note: Further Development Approvals may be required for sites (e.g. sites impacted by flooding and overland flows) proposed to import material from or export material to, prior to commencement of such work.

VEGETATION CLEARING

- 31. Any vegetation clearing as a result of this approval (e.g. along new boundary fence lines) is to comply with the following:
 - A. Ensure that an accredited fauna spotter/wildlife consultant* is present to check all potential habitat prior to vegetation removal or earthworks. The accredited fauna spotter/wildlife consultant:
 - a. inspect vegetation approved for removal (or any dams to be removed or dewatered) and advise contractors when it is appropriate to commence works;
 - clearly mark (flag) vegetation found to contain fauna or fauna habitat (such as tree hollows, arboreal termite mounds, stick nests or possum drays with flagging tape), and visually and verbally communicate this information to the tree feller to ensure flagged trees are not felled until authorised by the fauna spotter;
 - c. Where native vertebrate animals are found, clearing must only continue in coordination with a fauna spotter. All native vertebrate animals located within, on and amongst vegetation or areas of vegetation approved for clearing, are only to be managed under the guidance of the fauna spotter; and
 - d. Keep and maintain accurate records of all animal captures, incidents and disposals for the site and a report prepared for Council and other relevant authorities within one month of completion of the project.
 - *An accredited Fauna Spotter/ Wildlife Consultant is a person or company holding a current Rehabilitation Permit Spotter Catcher issued by the Department of Environment and Science under the *Nature Conservation (Animals) Regulation 2020.*
 - B. Any clearing of koala habitat trees must ensure the clearing is carried out in a way the complies with the sequential clearing conditions in Part 3 section 10 of the Nature Conservation (Koala) Conservation Plan 2017.

Note: Koala Habitat Trees are defined as:

a. a tree of the Corymbia, Melaleuca, Lophostemon or Eucalyptus genera that is edible by koalas; or

At all times.

- b. a tree of a type typically used by koalas for shelter, including, for example, a tree of the Angophora genus.
- C. Limit the felling of habitat and hollow bearing trees to the following methods:
 - segmental removal of the tree, with hollow-bearing limbs being checked by the wildlife spotter and cleared of fauna using a cherry picker;
 - segmental removal of the tree, with hollow-bearing limbs plugged and lowered to the ground for inspection by the wildlife spotter;
 - c. use of an excavator with vertical grab to lower the main trunk; or
 - d. a combination of the above methods.
- D. Preserve valuable habitat features such as large fallen logs, log piles, rock piles or outcrops wherever practicable through the translocation and re-establishment in coordination with the wildlife spotter.
- E. Ensure compliance with AS 4970 2009 Protection of trees on development sites, including but not limited to the implementation of a 'Tree Protection Zone' where trees are to be retained onsite and undertake the following:
 - a. install protective fencing to prevent any damage to areas not in the approved vegetation clearing area in general accordance with Section 4.3 of AS 4970 - 2009;
 - b. provide signs identifying the 'Tree Protection Zone' on exclusion fencing that are clearly visible from all areas within the development site within 20 metres of the exclusion fencing; and
 - c. ensure all trees to be retained within allotments are protected from harm during works on site. Ensure activities such as traffic, stockpiling and compaction are excluded from areas of retained vegetation particularly within the tree protection zones of retained trees.
- F. Ensure vegetation and rubble piles are not left to serve as a refuge for displaced or roaming wildlife through the implementation of the following measures:
 - a. immediately (within 12 hours) remove or destroy such materials; or
 - ensure old (>12 hours) piles of felled vegetation are treated as potential wildlife habitat and inspected by a wildlife spotter catcher prior to removal or destruction
- G. Ensure all vegetation cleared as a result of this development approval and requiring disposal is disposed of:
 - a. on the premises for landscaping and sediment and erosion control purposes (for example as mulch); and/or
 - at a waste disposal facility operated by Council provided that the waste is delivered to the waste disposal facility in a manner and form which allows it to be mulched at the facility; and/or
 - c. in such other environmentally responsible manner as meets with the written approval of the Council; and
 - d. ensure any vegetation cleared as a result of this development approval is not burnt or incinerated except for the purpose of domestic heating inside a dwelling on the subject site.

MANDATORY COUNCIL INSPECTIONS 32. The following inspections must be attended by Council's delegated At all times. officer, the supervising engineer (a suitably qualified RPEQ) and the Principal Contractor: a. Prestart meeting; b. Prior to backfilling of any stormwater drainage works; c. At the time of spreading topsoil; d. Structural steel inspection prior to pouring of any structural concrete: e. Prior to back filling road crossings (during construction of new roads, refer to condition on 'under boring' otherwise); f. Following preparation and compaction of road sub-grade; g. Following placement and compaction of each road pavement layer and prior to laying of the next pavement layer or surfacing layer; h. Finished pavement surface prior to any bitumen primer-seal or prime or asphalt surfacing. A minimum two (2) business days' written notice must be provided to Council requesting attendance for above inspections. On Maintenance inspection (refer to on-maintenance requirements); j. Off Maintenance inspection (further to a minimum 12 months defects liability period); A minimum five (5) business days' written notice must be provided to Council requesting attendance for maintenance inspections. ON MAINTENANCE REQUIREMENTS Ensure that following works will be completed prior to On-maintenance Prior to request for ona. Stabilise adequately all unstable or disturbed soil surfaces against maintenance. erosion (minimum 80% stabilised). b. Cover all dispersible soils exposed during soil disturbing activities with a minimum 100mm layer of non-dispersible soil before being covered with vegetation, mulch, erosion control blankets or infrastructure. c. All approved landscaping works have been completed. d. Install Kerb markers to identify the location of crossroad services e.g. water, electricity, telecommunication, gas etc. 34. Submit the following to Council prior to the on-maintenance inspection: Prior to request a. Evidence of Bond Payment(s) as per relevant conditions. for onb. Completed Inspection Check Lists (ITP) and all inspection and test maintenance. data in its entirety; c. Originals of relevant test results; d. Certification from a suitably qualified Registered Professional Engineer Queensland (RPEQ) stating that works have been undertaken in accordance with the approved plans, approval conditions and any agreed variations; e. CCTV footage and an inspection report for underground stormwater drainage works along with a letter from a suitably

qualified and experienced RPEQ stating that CCTV inspection report and video had been reviewed and rectification works were

successful and satisfactory.

f. Geotechnical and structural certificates (where applicable); Payment of any outstanding Fees and Permits; g. h. Any other relevant document that may be required by Council; Certification from a suitably qualified Registered Professional Engineer Queensland (RPEQ) that stormwater drainage works as a part of development works for the subdivision has been constructed to enable slab on ground construction for residential dwellings in lots and areas of lot established above Q100 flood line (provide a layout plan indicating building envelopes, if required for clarity). "As Constructed" data for [stormwater drainage, roadworks and j. earthworks where applicable]: i. In digital format all construction details compatible with IPWEAQ's Asset Design and As Constructed (ADAC) version 4.1 format with all details and values (e.g. survey levels, material types) matching the associated As-Constructed drawing(s). The electronic file will conform to the ADAC requirements including an electronic signature by a suitably qualified RPEQ / Registered Cadastral Surveyor where appropriate. The levels and positions of infrastructure must be referenced to GDA 94 (Zone 56) coordinate system and AHD. ii. A full set of approved drawings in PDF format that are clear and legible when printed at A3 scale with red-lined marked-up (strike through the original design data where applicable) showing changes to construction materials, design levels, locational details and other amendments from approved design that may have approved during the construction of approved Operational iii. Each drawing marked as 'As Constructed' and signed by a suitably qualified RPEQ/ Registered Cadastral Surveyor. iv. A written confirmation from a Registered Cadastral Surveyor verifying the accuracy of the locational details, relative levels, boundaries and alignments as shown on the drawing(s). v. Details are to include any redundant and/or removed assets as well as the details of the immediate existing infrastructure where new works connect to an existing stormwater network. 35. Submit to Council, a written request for an on-maintenance inspection Prior to issued by the developer's certifying Engineer (RPEQ) stating that all acceptance onapproved works have been completed and are ready for Council maintenance. inspection. Rectify any defects identified by Council during the on-maintenance 36. Prior to period. Defects must be remedied under the direction of the supervising acceptance offmaintenance. engineer (RPEQ). 37. Upon completion of the remedial works, the supervising engineer must Prior to request Council for another inspection of remedied works. acceptance offmaintenance. **MAINTENANCE PERIOD** The works that will become Council's infrastructure will be subject to a Prior to minimum twelve (12) month maintenance period, commencing from the acceptance off-On-Maintenance date stipulated by the assessment manager in 'On maintenance. Maintenance' correspondence.

ON/OFF MAINTENANCE				
39.	Undertake any further inspections, testing or analysis required, due to	At all times.		
33.	failure of work to meet specifications or where the testing previously	ric an enrics.		
	provided is considered insufficient on behalf of the Principal Contractor			
	by a NATA accredited entity, as directed by the Council further to the			
	initial on/off-maintenance inspection.			
40.	Provide a letter from a suitably qualified and experienced RPEQ stating	At all times.		
	that report and test results had been reviewed and proposed			
	rectification works for Council approval.			
41.	Undertake any rectification works further to a written approval from the	At all times.		
	Council.			
42.	Council is not liable for the rectification of or compensation for any	At all times.		
	damage caused in the testing or analysis process should work be found			
	to be not constructed to specification or of poor quality and not			
	satisfactory by Council.			
43.	The applicant and supervising engineer are responsible and liable for the	At all times.		
	rectification of defects, materials and works.			
44.	The Council reserves the right to call on the applicant or supervising	At all times.		
	engineer to rectify any works that have been found to not comply with			
	the Certificates received or for the safety or health of the community or			
	protection of infrastructure where Council deems it necessary.			
	MAINTENANCE			
45.	The Council reserves the right to extend the maintenance period for a	At all times.		
	period determined by the Council pending the performance of the			
	Council infrastructure, landscaping, erosion and sediment control and			
	earthworks during the initial maintenance period. The above			
	performance monitoring process to continue until any matters are			
4.6	resolved to Council's satisfaction.	A La Hattara		
46.	The Council reserves the right to extend the maintenance period to allow	At all times.		
	establishment of approved landscaping works and grass coverage (of 80% except in areas that has dispersible or erosive soils characteristics)			
	or request to provide an alternative permanent erosion control measure			
	acceptable to Council for affected areas;			
	a. in the event it is proposed to provide grass seeding or hydro			
	mulching at off-maintenance inspection to address any grass			
	coverage issues to allow establishment.			
	b. in the event the region is experiencing an unfavourable climate			
	conditions for the establishment of approved landscaping works or			
	grass coverage at the time of off-maintenance inspection.			
47.	Comply with the following conditions prior to Off-maintenance	Prior to request		
	inspection:	for off-		
	a. Fill and grade the remaining unsealed verge area or reinstate any	maintenance.		
	areas subject to erosion and must be either fully turfed or grassed			
	to achieve 80% grass coverage.			
	b. All the other areas disturbed during construction works (including			
	areas where water management works are constructed) must be			
	either fully turfed or grassed to achieve 80% grass coverage.			
48.	Submit to Council a Closed Circuit Television camera (CCTV) inspection	Prior to request		
	undertaken for underground stormwater drainage works no more than	for off-		
	2 weeks prior to the off maintenance inspection along with a letter from	maintenance.		

	a suitably qualified and experienced RPEQ stating that CCTV inspection report and video had been reviewed and identifying any issues.	
49.	The works will be accepted Off Maintenance only where the works have been suitably maintained to engineer or manufacturer's specifications and any rectification works approved by the Council has been completed to Council's satisfaction and Council standards.	At all times.
50.	All works must be fully completed to RPEQ Certified design and specifications, and the assessment manager must be satisfied that the works have been properly completed and landscaping and grass cover established.	At all times.
51.	The maintenance bond will be entirely forfeited to Council should there be any failure by the applicant to undertake any such works considered by Council as necessary, to rectify any non-compliant works and to protect public safety. In the event that the bond is insufficient to address the non-compliant works, Council reserves the right to seek restitution. After expiration of the maintenance period and where required maintenance is suitably undertaken to Council's satisfaction, the bond will be returned accordingly, after the project is accepted offmaintenance.	At all times.
52.	Undertake any necessary maintenance or repairs to defects and/or damage to any works undertaken in relation to this approval, even where damage has resulted from a third-party activity prior to Council accepting work off-maintenance.	At all times.

ADVISORY NOTES

- (i) All works associated with this approval may not start until all subsequent approvals have been obtained, and its conditions complied with.
- (ii) Any additions or modifications to the approved use (not covered in this approval) may be subject to further application for development approval.
- (iii) The maintenance bond will be entirely forfeited to Council should there be any failure by the applicant to undertake any such works considered by Council as necessary, to rectify any noncompliant works and to protect public safety. If the bond is insufficient to address the noncompliant works, Council reserves the right to seek restitution.
- (iv) In approving plans and specifications for this project, Council has carried out an audit check of information submitted by Van Der Meer Consulting Pty Ltd. Accordingly, Council has placed reliance on the certificate of design signed by the Registered Professional Engineer Queensland (RPEQ) that the Approved Plans and specifications are correct and in accordance with required engineering standards. The RPEQ bears full responsibility for all aspects of the engineering design. Council reserves the right to require further amendments and/or additions at a later stage, should design errors become apparent.

(v) Fire ants

Biosecurity Queensland should be notified on 13 25 23 of proposed development(s) occurring in the fire ant biosecurity zone before operational works commence. It should be noted that works involving fire ant carrier materials may be subject to movement controls and failure to obtain necessary approvals from Biosecurity Queensland is an offence.

It is a legal obligation to report any sighting or suspicion of fire ants within 24 hours to Biosecurity Queensland on 13 25 23.

The Fire Ant Restricted Area as well as general information can be viewed on the <u>DAF website</u>.

(vi) Biosecurity

Ensure all prohibited and restricted biosecurity matter under the Biosecurity Act 2014 are removed appropriately prior to conducting any works on the site.

Everyone is obligated under the *Biosecurity Act 2014* to take all reasonable and practical steps to minimise the risks associated with invasive plants under their control. More information on restricted and invasive plants as well as your general biosecurity obligation (GBO) can be viewed on the <u>Business Queensland website</u>.

(vii) Cultural heritage

The Aboriginal Cultural Heritage Act 2003 requires anyone who carries out a land use activity to exercise a duty of care. Further information on cultural heritage duty of care is available on the <u>Department of Aboriginal and Torres Strait Islander Partnerships</u> (DATSIP) website:

The DATSIP has established a <u>register and database</u> of recorded cultural heritage matters, which is also available on the Department's website:

Should any aboriginal, archaeological or historic sites, items or places be identified, located or exposed during construction or operation of the development, the *Aboriginal Cultural Heritage Act 2003* requires all activities to cease. Please contact DATSIP for further information.

Advice for Urban Utilities

On 1 July 2014, Urban Utilities became the assessment manager for the water and wastewater aspects of development applications. An application will need to be made directly to Urban Utilities for water supply connections for the proposed development.

Appeal Rights

Extract from the Planning Act 2016

Chapter 6 Dispute resolution

Part 1 Appeal rights

229 Appeals to tribunal or P&E Court

- (1) Schedule 1 states-
 - (a) matters that may be appealed to-
 - (i) either a tribunal or the P&E Court; or
 - (ii) only a tribunal; or
 - (iii) only the P&E Court; and
 - (b) The person-
 - (i) who may appeal a matter (the appellant); and
 - (ii) who is a respondent in an appeal of the matter; and
 - (iii) who is a co-respondent in an appeal of the matter; and
 - (iv) who may elect to be a co-respondent in an appeal of the matter.
- (2) An appellant may start an appeal within the appeal period.
- (3) The appeal period is-
 - (a) for an appeal by a building advisory agency 10 business days after a decision notice for the decision is given to the agency; or
 - (b) for an appeal against a deemed refusal at any time after the deemed refusal happens; or
 - (c) for an appeal against a decision of the Minister, under chapter 7, part 4, to register premises or to renew the registration of premises 20 business days after a notice us published under section 269(3)(a) or (4); or
 - (d) for an appeal against an infrastructure charges notice 20 business days after the infrastructure charges notice is given to the person; or
 - (e) for an appeal about a deemed approval of a development application for which a decision notice has not been given 30 business days after the applicant gives the deemed approval notice to the assessment manager; or
 - (g) for any other appeal 20 business days after a notice of the decision for the matter, including an enforcement notice, is given to the person.

Note – See the P&E Court Act for the court's power to extend the appeal period.

- (4) Each respondent and co-respondent for an appeal may be heard in the appeal.
- (5) If an appeal is only about a referral agency's response, the assessment manager may apply to the tribunal or P&E Court to withdraw from the appeal.
- (6) To remove any doubt, it is declared that an appeal against an infrastructure charges notice must not be about-
 - (a) the adopted charge itself; or
 - (b) for a decision about an offset or refund
 - the establishment cost of trunk infrastructure identified in a LGIP; or
 - (ii) the cost of infrastructure decided using the method included in the local government's charges resolution.

230 Notice of appeal

- (1) An appellant starts an appeal by lodging, with the registrar of the tribunal or P&E Court, a notice of appeal that—
 - (a) is in the approved form; and
 - (b) succinctly states the grounds of the appeal.
- (2) The notice of appeal must be accompanied by the required fee.
- (3) The appellant or, for an appeal to a tribunal, the registrar must, within the service period, give a copy of the notice of appeal to—
 - (a) the respondent for the appeal; and
 - (b) each co-respondent for the appeal; and

- (c) for an appeal about a development application under schedule 1, table 1, item 1 each principal submitter for the development application; and
- (d) for and appeal about a change application under schedule 1, table 1, item 2 each principal submitter for the change application; and
- (e) each person who may elect to become a co-respondent for the appeal, other than an eligible submitter who is not a principal submitter in an appeal under paragraph (c) or (d); and
- (f) for an appeal to the P&E Court the chief executive; and
- (g) for an appeal to a tribunal under another Act any other person who the registrar considers appropriate.
- (4) The service period is-
 - (a) if a submitter or advice agency started the appeal in the P&E Court 2 business days after the appeal has started; or
 - (b) otherwise 10 business days after the appeal is started.
- (5) A notice of appeal given to a person who may elect to be a co-respondent must state the effect of subsection (6).
- (6) A person elects to be a co-respondent by filing a notice of election, in the approved form, within 10 business days after the notice of appeal is given to the person.

231 Other appeals

- (1) Subject to this chapter, section 316(2), schedule 1 and the P&E Court Act, unless the Supreme Court decides a decision or other matter under this Act is affected by jurisdictional error, the decision or matter is non-appealable.
- (2) The *Judicial Review Act 1991*, part 5 applies to the decision or matter to the extent it is affected by jurisdictional error.
- (3) A person who, but for subsection (1) could have made an application under the *Judicial Review Act 1991* in relation to the decision or matter, may apply under part 4 of that Act for a statement of reasons in relation to the decision or matter.
- (4) In this section-

decision includes-

- (a) conduct engaged in for the purpose of making a decision; and
- (b) other conduct that relates to the making of a decision; and
- (c) the making of a decision or failure to make a decision; and
- (d) a purported decision; and
- (e) a deemed refusal.

non-appealable, for a decision or matter, means the decision or matter-


- (a) is final and conclusive; and
- (b) may not be challenged, appealed against, reviewed, quashed, set aside or called into question in any other way under the Judicial Review Act 1991 or otherwise, whether by the Supreme Court, another court, a tribunal or another entity; and
- (c) is not subject to any declaratory, injunctive or other order of the Supreme Court, another court, a tribunal or another entity on any ground.


232 Rules of the P&E Court

- (1) A person who is appealing to the P&E Court must comply with the rules of the court that apply to the appeal.
- (2) However, the P&E Court may hear and decide an appeal even if the person has not complied with the rules of the P&E Court.

PROPOSED SUBDIVISION

PARKLAKE, ADARE - STAGES 4 AND 5 174 ADARE ROAD, ADARE, QLD 4343













ER MEER WITHOUT	PARK LAKE ADARE PTY LTD
OR THE R (QLD)	PO BOX 4107 SPRINGFIELD QLD 4300
FOR ING HAS OR	
	SCALE
IATION	

SCALE 1:5000

PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343

FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION DRAFTSPERSON SHEET SIZE AS SHOWN | 15/04/24 REVISION BR242001 C4000

CIVIL ENGINEERING DRAWINGS

EROSION AND SEDIMENT CONTROL PLAN - SHEET 1

EROSION AND SEDIMENT CONTROL PLAN - SHEET 2 EROSION AND SEDIMENT CONTROL PLAN - SHEET 3

EROSION AND SEDIMENT CONTROL DETAILS

EROSION AND SEDIMENT CONTROL NOTES

BULK EARTHWORKS PLAN - SHEET 1

BULK EARTHWORKS PLAN - SHEET 2

BULK EARTHWORKS PLAN - SHEET 3

BULK EARTHWORKS DETAILS

PAVEMENT PLAN - SHEET 1 PAVEMENT PLAN - SHEET 2

PAVEMENT PLAN - SHEET 3

ROADWORKS PLAN - SHEET 1

ROADWORKS PLAN - SHEET 2

IROADWORKS PLAN - SHEET 3

INTERSECTION DETAILS

DRAINAGE CATCHMENT PLAN

DRAINAGE PLAN - SHEET 1

DRAINAGE PLAN - SHEET 2

DRAINAGE PLAN - SHEET 3

DRAINAGE CALCULATIONS

DRAINAGE BIO RETENTION BASIN DETAILS

WATER RETICULATION COVER SHEET

WATER RETICULATION PLAN - SHEET 1

WATER RETICULATION PLAN - SHEET 2

WATER RETICULATION PLAN - SHEET 3

BUSHFIRE TRAIL 3 LONGITUDINAL SECTION - SHEET 1 BUSHFIRE TRAIL 3 LONGITUDINAL SECTION - SHEET 2

BUSHFIRE TRAIL 3 LONGITUDINAL SECTION - SHEET 3

BUSHFIRE TRAIL 4 LONGITUDINAL AND CROSS SECTIONS

BUSHFIRE TRAIL 5 LONGITUDINAL SECTION - SHEET 1 BUSHFIRE TRAIL 5 LONGITUDINAL SECTION - SHEET 2

BUSHFIRE TRAIL 5 LONGITUDINAL SECTION - SHEET 3

BUSHFIRE TRAIL 6 LONGITUDINAL AND CROSS SECTIONS

BUSHFIRE TRAIL 5 CROSS SECTIONS - SHEET 1

BUSHFIRE TRAIL 5 CROSS SECTIONS - SHEET 2 BUSHFIRE TRAIL 5 CROSS SECTIONS - SHEET 3

BUSHFIRE TRAIL 3 CROSS SECTIONS - SHEET 1

BUSHFIRE TRAIL 3 CROSS SECTIONS - SHEET 2 BUSHFIRE TRAIL 3 CROSS SECTIONS - SHEET 3

BUSHFIRE TRAIL 3 AND 4 PLAN

BUSHFIRE TRAIL 5 AND 6 PLAN

BUSHFIRE TRAIL DETAILS

DRAINAGE LONGITUDINAL SECTIONS - SHEET 1 DRAINAGE LONGITUDINAL SECTIONS - SHEET 2

ROADWORKS DETAILS

SIGNS AND PAVEMENT MARKING PLAN - SHEET 1 SIGNS AND PAVEMENT MARKING PLAN - SHEET 2

SIGNS AND PAVEMENT MARKING PLAN - SHEET 3

ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET

ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET 2

ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET 3 ROAD LONGITUDINAL SECTION - NEWLAND PLACE - SHEET 4

ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 1

ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 2

ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 3

ROAD CROSS SECTIONS - NEWLAND PLACE - SHEET 4

ROAD CROSS SECTIONS - BURTON CRESCENT - SHEET 1

ROAD CROSS SECTIONS - BURTON CRESCENT - SHEET 2 ROAD CROSS SECTIONS - BURTON CRESCENT - SHEET 3

ROAD LONGITUDINAL SECTION - BURTON CRESCENT - SHEET 1

ROAD LONGITUDINAL SECTION - BURTON CRESCENT - SHEET 2

SHEET TITLE

SHEET NUMBER

C4003

C4004

C4101

C4102

C4190

C4191

C4200

C4201

C4202

C4290

C4301

C4302

C4401

C4430

C4432

C4450

C4452

C4453

C4455

C4456

C4457

C4458

C4459

C4461

C4490

C4502

C4503

C4550

C4560

C4601

C4603

C4701

C4703

C4705

C4709

C4711

C4713

C4715

COVER SHEET

STANDARD NOTES

SITE PLAN - SHEET

SITE PLAN - SHEET 2

SITE PLAN - SHEET 3

	STAGES 4 AND 5
	DRAWING TITLE
)m	COVER SHEET

GENERAL NOTES

- G1. ALL LEVELS SHALL BE OBTAINED FROM ESTABLISHED BMS OR SSM.
- G2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK.
- G3. ALL WORKS ARE TO BE UNDERTAKEN IN ACCORDANCE WITH COUNCIL'S SPECIFICATIONS AND THE DIRECTIONS OF THE SUPERINTENDENT.
- G4. DIMENSIONS MUST NOT BE SCALED FROM DRAWINGS.
- G5. CONTRACTOR TO ENSURE THAT ALL ROADWORKS ARE SMOOTHLY TRANSITIONED TO EXISTING LEVELS FREE FROM ABRUPT CHANGES.
- G6. THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE CARRIED OUT BY A REGISTERED SURVEYOR. FURTHER, THE LOCATION OF RECOVERY MARKS SHOULD BE VERIFIED AND CONFIRMED BY THE CONTRACTOR AND ANY DISCREPANCIES SHOULD BE CLARIFIED IN WRITING WITH THE SUPERINTENDENT PRIOR TO THE COMMENCEMENT
- G7. AT COMPLETION OF WORKS ALL ADJOINING DISTURBED AREAS ARE TO BE REINSTATED TO THE "AS FOUND" CONDITION.
- G8. THE CONTRACTOR SHALL ENSURE ALL AREAS DRAIN WITH A MINIMUM FALL OF 1% (1:100) GRADE TO OUTLETS UNLESS INDICATED OTHERWISE. NO WORKS SHALL CAUSE PONDING OF STORMWATER ON UPSTREAM PROPERTIES OR CONCENTRATE RUNOFF ONTO DOWNSTREAM PROPERTIES.
- G9. THESE PLANS SHALL BE READ IN CONJUNCTION WITH APPROVED LANDSCAPE, ARCHITECTURAL, ELECTRICAL, RETICULATION, WATER AND SEWER DRAWINGS AND SPECIFICATIONS AND OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED.
- G10. THE CONTRACTOR SHALL ENSURE THAT ALL PAVEMENTS GRADE EVENLY BETWEEN NOMINATED RL'S ON PLAN AND NO POND OF WATER OCCURS.
- G11. ALL DIMENSIONS ARE IN METERS UNLESS STATED OTHERWISE. ALL LEVELS ARE EXPRESSED IN METERS.
- G12. DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURE IN A STABLE CONDITION AND ENSURING NO PART SHALL BE OVERSTRESSED UNDER CONSTRUCTION ACTIVITIES.
- G13. WORKMANSHIP AND MATERIALS ARE TO BE IN ACCORDANCE WITH THE RELEVANT CURRENT S.A.A. CODES INCLUDING ALL AMENDMENTS, AND THE LOCAL STATUTORY AUTHORITIES, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- G14 THE APPROVAL OF A SUBSTITUTION SHALL BE SOUGHT FROM THE ENGINEER BUT IS NOT AN AUTHORIZATION FOR AN EXTRA. ANY EXTRAS INVOLVED MUST BE TAKEN UP WITH THE SUPERINTENDENT BEFORE THE WORK COMMENCES.
- G15 THE CONTRACTOR IS TO EMPLOY A QUALIFIED GEOTECHNICAL ENGINEER
 AS REQUIRED FOR ALL GEOTECHNICAL ASPECTS OF THE BUILDING WORKS.
 REFER TO FOUNDATION, GROUNDWORKS AND RETENTION/SHORING NOTES.
 REFER ALSO TO THE GEOTECHNICAL REPORT FOR THIS PROJECT.
- G16 ORIGINAL SURVEY WAS COMPLETED BY BPLANNED & SURVEYED PH.1300 275 266

SUBGRADE PREPARATION

- RW1. REMOVE ALL VEGETATION, TOPSOIL AND DELETERIOUS MATERIAL FROM AREA OF PROPOSED BUILDING PLATFORM AND PAVEMENTS.
- RW2. PROOF ROLL EXPOSED SUB GRADE TO ACHIEVE A MINIMUM COMPACTION OF 98% STANDARD MAXIMUM DRY DENSITY (SMDD), DETERMINED BY THE STANDARD COMPACTION TEST IN ACCORDANCE WITH CURRENT AUSTRALIAN STANDARD 1289.5.1.1.
- RW3. REMOVE ANY SOFT, HEAVING, WET OR UNSTABLE AREAS IDENTIFIED DURING PROOF ROLLING AND REPLACE USING SELECT IMPORTED FILL COMPACTED IN LAYERS NOT EXCEEDING 200mm MEASURED LOOSE TO ACHIEVE A MINIMUM 98% STANDARD MAXIMUM DRY DENSITY.
- RW4. NOTE THAT THE SITE IS UNDERLAIN BY EXISTING SERVICES AND COMPACTION UTILISING VIBRATION MAY NOT BE SUITABLE IN THE VICINITY OF UNDERGROUND SERVICES.
- RW5. ANY FILL REQUIRED TO RAISE LEVELS TO BULK EARTHWORKS TO WITHIN 50mm OF NOMINATED LEVELS IS TO BE APPROVED GRANULAR MATERIAL COMPACTED IN LAYERS NOT EXCEEDING 300mm MEASURED LOOSE TO 98% STANDARD MAXIMUM DRY DENSITY WITHIN 2% OF STANDARD OPTIMUM MOISTURE CONTENT (SOMC).
- RW6. THE CONTRACTOR IS TO PROVIDE CERTIFICATION TO THE EFFECT THAT EARTHWORKS COMPACTION TO 98% STANDARD MAXIMUM DRY DENSITY, (AS 1289 E1.1, E4.1) HAS BEEN ACHIEVED, UNLESS OTHERWISE AGREED IN WRITING BY SITE SUPERINTENDENT.
- RW7. THE CONTRACTOR IS TO PROVIDE TO THE SITE SUPERINTENDENT A SURVEY CONFIRMATION FROM A REGISTERED SURVEYOR, CONFIRMING BULK EARTHWORKS LEVELS AS WITHIN +/-50mm OF LEVELS NOMINATED.
- RW8. SUBGRADE REPLACEMENT MATERIAL IS TO CONSIST OF CLEAN, UNCONTAMINATED, WELL-GRADED MATERIAL WITH A MAXIMUM PARTICLE SIZE OF 75mm, WITH 80% LESS THAN 20mm, AND A SOAKED C.B.R. GREATER THAN 10% AND A PLASTICITY INDEX LESS THAN 12.
- RW9. BACK FILLING FOR SERVICE TRENCHES AND REMOVED SERVICES OR PITS OR FOUNDATIONS IS TO USE APPROVED WELL-GRADED GRANULAR MATERIAL WITH MINIMUM VOIDS, (EITHER SELECT INSITU OR IMPORTED FILL), COMPACTION AS SPECIFIED ABOVE.
- RW10. ALL EARTHWORKS TO BE UNDERTAKEN IN ACCORDANCE WITH AS3798-1996: GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS.

DRAWN DATE

GENERAL EARTHWORKS

- E1. THE SITE OF THE WORKS SHALL BE PREPARED BY STRIPPING ALL EXISTING TOPSOIL, FILL AND VEGETATION.
- E2. COMPACT SUBGRADE TO 98% OF THE STANDARD MAXIMUM DRY DENSITY WHEN TESTED IN ACCORDANCE WITH AUSTRALIAN STANDARD AS 1289 TESTS E.1.1. OR E.1.2. THE EXPOSED SUBGRADE SHOULD BE PROOF ROLLED TO DETECT ANY SOFT OR WET AREAS WHICH SHOULD BE LOCALLY EXCAVATED AND BACK FILLED WITH SELECTED MATERIAL. THE BACK FILLING MATERIAL SHALL BE IMPORTED GRANULAR FILL OF LOW PLASTICITY, PREFERABLY CRUSHED SANDSTONE, AND TO BE PLACED IN LAYERS NOT EXCEEDING 300mm LOOSE THICKNESS AND COMPACTED TO 98% OF STANDARD MAXIMUM DRY DENSITY WITHIN 2% OF STANDARD OPTIMUM MOISTURE CONTENT. SITE WORKS ARE TO BE BATTERED TO ADJACENT PROPERTY LEVELS.
- E3. NO STORMWATER IS TO POND ON ADJOINING PROPERTIES. THE SITE SHALL BE GRADED AND DRAINED SO THAT STORMWATER WILL BE DIRECTED AWAY FROM THE BUILDING PLATFORM. STORMWATER DRAINAGE SHALL BE PROVIDED AND MAINTAINED THROUGHOUT THE COURSE OF CONSTRUCTION. ALL STORMWATER RUNOFF SHALL BE GRADED AWAY FROM THE DWELLING AND DISPOSED OF VIA SURFACE CATCHDRAINS AND STORMWATER COLLECTION PITS.
- E4. ENSURE ALL RETAINING WALLS ARE CONSTRUCTED WITH ADEQUATE SUBSOIL DRAINAGE.

GROUND WORKS AND EXCAVATION

- GW1. ALL GROUND WORKS AND EXCAVATION SHALL BE IN ACCORDANCE WITH GEOTECHNICAL REPORT: 93323.00.R.01.Rev01.
- GW2. SEPARATE AND REMOVE ALL TOPSOIL, NON SOIL MATERIAL, CONCRETE, VEGETATION, BRICKBATS, TIMBER, ROOT AFFECTED SOIL AND EXISTING FILL. STORE TOPSOIL IF REQUIRED.
- GW3. ALL EXCAVATIONS SHALL BE FINISHED CLEAN AND HORIZONTAL AND SHALL NOT UNDERMINE FOOTINGS. WALLS etc...
- GW4. PROOF ROLL WITH AN 8 TONNE ROLLER, REPLACE ANY SOFT MATERIAL WITH APPROVED FILL AND RE-COMPACT. GEOTECHNICAL ENGINEER TO APPROVE
- GW5. THE FILL IS TO BE PLACED AND COMPACTED IN LAYERS OF MAXIMUM LOOSE THICKNESS 300mm.
- GW6. TOP LAYER OF PAVED AREAS TO BE COMPACTED TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY, GEOTECHNICAL ENGINEER TO VERIFY.
- GW7. ALL PERMANENT EMBANKMENTS TO BE COMPACTED IN 200 mm
 LAYERS AS PER NOTE GW6 AND AT A MAXIMUM SLOPE OF 1 VERTICAL TO 2.5
 HORIZONTAL UNLESS NOTED OTHERWISE. SHOULD DRAINAGE BE REQUIRED THEN SUBMIT DETAILS TO THE ENGINEER.
- GW8. ALL GROUND WORKS SHALL BE TESTED BY AN APPROVED GEOTECHNICAL ENGINEER TO A LEVEL 1 STANDARD IN ACCORDANCE WITH AS 3798 1996.
- GW9. ALL EXCAVATIONS TO BE INSPECTED AT REGULAR INTERVALS BY A GEOTECHNICAL ENGINEER.
- GW10. REFER TO ARCHITECTURAL DRAWINGS TO CONFIRM SETOUT OF BUILDINGS, CARPARKS ETC.
- ARE SHOWN.

GW11. THE LEVELS SHOWN ARE ONLY RELEVANT TO THE PLAN UPON WHICH THEY

- GW12. ALL CONTOURS AND LEVELS USED TO PRODUCE EARTHWORK DETAILS HAVE BEEN BASED ON SURVEYOR AND ARCHITECTS SURVEY INFORMATION.
- GW13. ALL FINISHED FLOOR LEVELS ARE TO BE CONFIRMED BY ARCHITECT.
- GW14. ALL EXISTING SERVICES ARE TO BE CAPPED OFF PRIOR TO ANY WORKS.
- GW15. A PRE-CONSTRUCTION MEETING SHALL BE HELD BETWEEN THE CONTRACTOR, THE GEOTECHNICAL ENGINEER, AND THE EARTHWORKS CONTRACTOR TO UNDERSTAND POTENTIAL DIFFICULTIES AND TO ORGANISE TESTING PROCEDURES. THE CONTRACTOR SHALL CONFIRM TO THE ENGINEER THAT THE MEETING HAS BEEN HELD.

DRAINAGE NOTES

- D1. PIT LEVELS SHOWN ON STORMWATER DRAINAGE PLANS ARE FOR INFORMATION. EXACT PIT LEVELS TO BE ADJUSTED TO SUIT FALLS IN PAVEMENT/LANDSCAPED AREA.
- D2. PITS GREATER THAN 1.2m DEEP TO BE FITTED WITH STEP IRONS.
- D3. DRAINAGE PIPES SHALL BE BACKFILLED WITH COMPACTED CLEAN SHARP SAND TO 200 ABOVE PIPE OBVERT. ADDITIONAL BACKFILL UNDER ROADS SHALL CONSIST OF CLASS 2 F.C.R. MATERIAL COMPACTED IN 200mm LAYERS TO 98% SMDD. UNDER LANDSCAPED AREAS ADDITIONAL BACKFILL SHALL CONSIST OF GRANULAR MATERIAL COMPACTED IN 200mm LAYERS TO 95% SMDD.

 A 3m LENGTH OF 100 Ø SLOTTED AGRICULTURAL LINE SURROUNDED BY GEOTECH STOCKING SHALL BE PROVIDED ON THE UPSTREAM SIDE OF ALL DITS
- D4. CONCRETE STORMWATER PIPES TO BE CLASS '3' UNDER ROADS AND CLASS '2' IN NON-TRAFFICED AREAS. ALL PIPES GREATER THAN 300Ø ARE TO BE RUBBER RING JOINTS U.N.O.
- D5. CONCRETE PITS GREATER THAN 1.0m DEEP TO BE REINFORCED WITH N12-200 EACH WAY CENTRED, MIN. 300 LAP, CONCRETE F'c 25MPa
- D6. 150Ø, 225Ø AND 300Ø uPVC PIPES TO BE SEWER GRADE PIPE UNDER TRAFFICABLE PAVEMENT. MIN. 400 COVER UNDER NON-TRAFFICABLE
- D7. PIT COVERS AND GRATED DRAINS IN TRAFFICABLE PAVEMENT TO BE AS 3996 CLASS D "HEAVY DUTY" AND IN NON-TRAFFICABLE AREAS TO BE AS 3996 CLASS C "LIGHT DUTY".
- D8. SUPERINTENDENT TO APPROVE LOCATION OF SUBSOIL OUTLET HEADWALLS IN ACCORDANCE WITH IPWEAQ STD DRG RS-142.

UTILITY SERVICES

- S1. CONDUITS TO BE PROVIDED FOR WATER AND ENERGY AUTHORITIES, TELSTRA AND OTHER SERVICES AS REQUIRED.
- S2. THE LOCATIONS OF UNDERGROUND SERVICES SHOWN ON THESE DRAWING'S HAVE BEEN PLOTTED FROM SURVEY AND AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE.
- 33. VAN DER MEER CANNOT GUARANTEE THAT THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS, ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN ARISING FROM ANY CAUSE WHATSOEVER.
- S4. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES SHALL BE REPORTED TO THE SUPERINTENDENT. CLEARANCES SHALL BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY.
- S5. CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ON SITE INCLUDING HAND EXCAVATION WHERE NECESSARY.
- 6. CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION OR FUTURE WORKS.
- S7. CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES.

TELSTRA - DUTY OF CARE NOTE:

TELSTRA'S PLANS SHOW ONLY THE PRESENCE OF CABLES AND PLANT. THEY ONLY SHOW THEIR POSITION RELATIVE TO ROAD BOUNDARIES, PROPERTY FENCES ETC. AT THE TIME OF INSTALLATION AND TELSTRA DOES NOT WARRANT OR UPHOLD THAT SUCH PLANS ARE ACCURATE THEREAFTER DUE TO CHANGES THAT MAY OCCUR OVER TIME. DO NOT ASSUME DEPTH OR ALIGNMENT OF CABLES OR PLANT AS THESE VARY SIGNIFICANTLY.

THE CONTRACTOR HAS A DUTY OF CARE WHEN EXCAVATING NEAR TELSTRA CABLES AND PLANT. BEFORE USING MACHINE EXCAVATORS TELSTRA PLANT MUST FIRST BE PHYSICALLY EXPOSED BY SOFT DIG POT HOLING TO IDENTIFY IT'S LOCATION. TELSTRA WILL SEEK COMPENSATION FOR DAMAGES CAUSED TO IT'S PROPERTY AND LOSSES CAUSED TO TELSTRA AND IT'S CUSTOMERS.

ELECTRICAL AND GAS NETWORK:

A MINIMUM OF 30 DAYS PRIOR TO COMMENCEMENT OF EXCAVATION WORKS THE SUBCONTRACTOR MUST CONTACT DIAL BEFORE YOU DIG.

RETAINING WALL GENERAL

- GR1. BASE MATERIAL SHALL BE COMPACTED TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY (SMDD) WITHIN 2% OF STANDARD OPTIMUM MOISTURE CONTENT (SMOC) DETERMINED BY THE STANDARD COMPACTION TEST IN ACCORDANCE WITH CURRENT AUSTRALIAN STANDARD 1289.5.1.1. MINIMUM ALLOWABLE BEARING PRESSURE OF 150 kPa. GEOTECHNICAL ENGINEER EMPLOYED BY CONTRACTOR TO INSPECT AND CONFIRM.
- GR2. DRAINAGE MATERIAL WITHIN AND IMMEDIATELY BEHIND THE WALL SHALL BE 12-20mm CLEAN AGGREGATE. DRAINAGE MATERIAL TO EXTEND A MINIMUM 300mm BEHIND WALL. COMPACT DRAINAGE MATERIAL.
 - ALTERNATIVELY, USE NO FINES CONCRETE, AS FOLLOWS:
 - CONCRETE STRENGTH N15.210kg/m3 PORTLAND CEMENT
 - MAXIMUM AGGREGATE SIZE 20 mm.
- W/C RATIO 0.45 TO 0.55.
 DENSITY 1600 TO 2000 kg/m3.
- GR3. INFILL SOIL SHALL BE CLASS 1 CONTROLLED FILL TO AS4678, OR AS SPECIFIED ON THE DRAWINGS. UNSUITABLE SOILS, SUCH AS HEAVY CLAYS OR ORGANIC SOILS WITH HIGH PLASTICITY, SHALL NOT BE USED IN THE REINFORCED SOIL MASS.
- GR4. SPREAD BACKFILL IN UNIFORM LIFTS OF 200mm UNCOMPACTED THICKNESS. COMPACT TO MINIMUM 95% OF SMDD.

 COMPACTION WITHIN 1.0 m BEHIND THE WALL SHALL BE ACCOMPLISHED BY USING A HAND-OPERATED PLATE COMPACTOR AND SHALL BEGIN BY RUNNING THE PLATE DIRECTLY ON THE BLOCK, THEN COMPACTING IN PARALLEL PATHS. PROGRESSIVELY AWAY FROM THE WALL FACE.
- GR5. WHERE ROADWAYS OR BUILDING STRUCTURES ARE LOCATED ABOVE THE REINFORCED ZONE, COMPACT TO 98% SMDD WITHIN 2% OF SOMC DETERMINED BY THE STANDARD COMPACTION TEST IN ACCORDANCE WITH CURRENT AUSTRALIAN STANDARD 1289.5.1.1. COMPACTION TESTING SHALL BE TAKEN AT 1.2m BEHIND THE WALL.

PAVEMENT

- F1. SUBGRADE SHALL BE PREPARED AS OUTLINED IN EARTHWORKS.
- F2. PAVEMENT MATERIAL SHALL CONSIST OF APPROVED OR RIPPED SANDSTONE, NATURAL GRAVEL OR FINE CRUSH ROCK AS PER COUNCIL SPECIFICATION.
- F3. PAVEMENT MATERIALS SHALL BE SPREAD IN LAYERS NOT EXCEEDING 150mm AND NOT LESS THEN 75mm COMPACTED THICKNESS. PAVEMENT MATERIALS SHALL BE SIZED AND OF A STANDARD OUTLINED IN AS1141.
- F4. CRUSHED OR RIPPED SANDSTONE SHALL BE MINUS 75mm NOMINAL SIZE DERIVED FROM SOUND, CLEAN SANDSTONE FREE FROM OVERBURDEN, CLAY SEAMS, SHALE AND OTHER DELETERIOUS MATERIAL.
- F5. PAVEMENT MATERIALS SHALL BE COMPACTED BY SUITABLE MEANS TO SATISFY THE FOLLOWING MINIMUM SPECIFICATIONS (AS PER AS1289.52)

DESCRIPTION MODIFIED DENSITY RATIO
SUB-BASE 98% MDD
BASE COURSE 98% MDD
ASPHALTIC CONCRETE 97% MDD

AND SUBJECT TO COUNCIL'S CONSTRUCTION SPECIFICATION.

- F6. TESTING FOR EACH LAYER SHALL BE UNDERTAKEN BY A N.A.T.A. REGISTERED LABORATORY IN ACCORDANCE WITH AS1289, AT NOT MORE THAN 50m INTERVALS AND A MINIMUM OF TWO PER LAYER. FURTHER FREQUENCY OF TESTING SHALL BE NO LESS THAN THAT REQUIRED BY AS3978-1996.
- F7. A MINIMUM GRAVEL LAYER 150-200mm ABOVE THE GEOGRID SHALL BE ADHERED TO AS PER SUPPLIER (GLOBAL SYNTHETICS) REQUIREMENTS AND SPECIFICATIONS.

AS CONSTRUCTED

PRIVATE WORKS (SITE CIVIL WORKS)

THE CONTRACTOR SHALL PROVIDE THE FOLLOWING AS-CONSTRUCTED DOCUMENTATION TO VAN DER

MEER PRIOR TO PRACTICAL COMPLETION OF CIVIL WORKS:

PW.01 A COMPLETE SURVEY OF COMPLETED SURFACE INCLUDING SURFACE LEVELS OF ALL

STRUCTURES INCLUDING BUT NOT LIMITED TO:

- STORMWATER MANHOLES AND PITS.
- BIO-RETENTION AREAS, INCLUDING BASE AND TOP OF FILTER TRENCH MATERIAL AND AREA INSTALLED, IF APPLICABLE.
- WATER SERVICE CONNECTION INCLUDING FITTINGS AND METERS.
- SEWERAGE PROPERTY CONNECTIONS INCLUDING MANHOLES.
- SEWER PUMP STATIONS, IF APPLICABLE
- PW.02 COPIES OF NATA TEST CERTIFICATE RESULTS IN RESPECT OF:
 THE COMPACTION OF FILL INCLUDING COMPACTION OF TRENCH BACKFILL.
- EARTHWORKS CERTIFICATION FROM GEOTECHNICAL RPEQ INCLUDING LEVEL 1 CERTIFICATION WHERE REQUIRED.
- THE SUB-GRADE CBR.
- THE SUB-GRADE COMPACTION.
- THE LOWER SUBBASE (CBR 15) MATERIAL QUALITY.
- THE LOWER SUBBASE (CBR 15) COMPACTION.
- THE SUB-BASE COURSE (CBR 45) MATERIAL QUALITY.
- THE SUB-BASE COURSE (CBR 45) COMPACTION.
 THE BASE COURSE (CBR 80) MATERIAL QUALITY.
- THE BASE COURSE (CBR 80) COMPACTION.
- THE PRIME OR PRIMER SEAL SPRAY AND APPLICATION RATES.

THE AC CORE TESTS

ANY CONCRETE TESTING REQUIRED.

CCTV VIDEO FOR UNDERGROUND STORMWATER INFRASTRUCTURE WORK. PW.03 DURING CONSTRUCTION, DIGITAL PHOTOGRAPHS MUST:

- BE TAKEN OF COMPLEX CONSTRUCTIONS OR INSTALLATIONS WHICH WILL BE BELOW GROUND LEVEL OR NOT VISIBLE AFTER CONSTRUCTION COMPLETION OR AS REQUESTED ON SITE.
- BE TAKEN PRIOR TO BACKFILLING.

 INCLUDE A CHANAGE OF EXACT LOCATION REFERENCE IN THE TITLE OF THE DIGITAL BUOTA.

 INCLUDE A CHANAGE OF EXACT LOCATION REFERENCE IN THE TITLE OF THE DIGITAL BUOTA.
- INCLUDE A CHAINAGE OR EXACT LOCATION REFERENCE IN THE TITLE OF THE DIGITAL PHOTO

 FILE
- BE DATE STAMPED.

COUNCIL WORKS

CW.01 TO PROVIDE AS CONSTRUCTED INFORMATION AS PER LOCAL COUNCIL SUBMISSION GUIDELINES REQUIREMENTS.

REINFORCED CONCRETE BLOCKWORK

- M1. CONCRETE BLOCKS SHALL BE BORAL 'CORE FILL BLOCKS', DOUBLE-U TYPE, OR SIMILAR APPROVED.
- M2. MINIMUM DURABILITY REQUIREMENTS:

LOCATION	SALT ATTACK RESISTANCE GRADE OF MASONRY UNIT	MORTAR CLASS	DURABILITY CLASS OF WALL TIES AND BUILT-IN COMPONENTS
INTERIOR MASONRY	GENERAL PURPOSE	М3	R3
EXTERIOR MASONRY ABOVE DAMP PROOF COURSE	GENERAL PURPOSE	M3	R3
BELOW DAMP PROOF COURSE OR IN CONTACT WITH GROUND	EXPOSURE	M4	R4

M3. MINIMUM STRENGTH REQUIREMENTS:

ELEMENT	STRENGTH OF MASONRY UNIT	MORTAR CLASS #
CONCRETE BLOCKWORK (REINF)	fuc = 15 MPa	M3

UNLESS A HIGHER CLASSIFICATION IS REQUIRED FOR DURABILITY (REFER NOTE M2).

- M4. LAY BOTTOM COURSE OF BLOCKS ON FULL MORTAR BED.
- ALL PERPENDS SHALL BE FILLED WITH MORTAR, EXCEPT WEEPHOLES.

 M5. ALL CORES SHALL BE GROUTED UNLESS NOTED OTHERWISE.
- M6. GROUT FOR CORE FILLING SHALL BE IN ACCORDANCE WITH AS3600, WITH THE FOLLOWING PROPERTIES:
- STRENGTH GRADE S20MAX. AGGREGATE SIZE 10mm

WALLS AS FOLLOWS

SLUMP 230mm ± 25mm
 MIN. CEMENT CONTENT 300kg/m³ M7. PROVIDE VERTICAL CONTROL JOINTS IN MASONRY

WALL TYPE	JOINT WIDTH	MAX JOINT SPACING
CONCRETE BLOCKWORK (REINF)	15mm	12m

- M7. AT CORNERS, CONTROL JOINTS SHALL BE WITHIN HALF THE SPECIFIED JOINTS SPACING FROM THE CORNER. JOINTS SHALL BE SEALED WITH AN APPROVED FLEXIBLE SEALANT. PROVIDE JOINTS TO MATCH JOINTS IN SUPPORTING SLABS.
- M8. PROVIDE CLEANOUT OPENINGS AT THE BASE OF ALL REINFORCED CORES AND REMOVE ALL MORTAR PROTRUSIONS BEFORE GROUTING. ADDITIONAL CLEANOUT OPENINGS SHALL BE PROVIDED ABOVE EACH HORIZONTAL POUR BREAK.
- M9. MAXIMUM HEIGHT OF POUR FOR GROUTING SHALL NOT EXCEED 3.6m FOR 190 LOCKWORK, AND 0.8m FOR 140 BLOCKWORK. STOP POUR 50mm BELOW TOP OF BLOCK TO PROVIDE KEY FOR SUBSEQUENT POUR.

M10. GROUT SHALL BE THOROUGHLY COMPACTED IN THE CORES BY RODDING OR MECHANICAL

CONCRETE

- C1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600 AND OTHER RELEVANT AUSTRALIAN STANDARDS.
- C2. CONCRETE SHALL BE SUPPLIED BY AN APPROVED MANUFACTURER IN
- ACCORDANCE WITH AS1379.
- SLUMP fc

C3. CONCRETE SHALL HAVE THE FOLLOWING PARAMETERS:

ELEMENT	SLUMP (mm)	AGGREGATE	f'c (MPa)	OTHER REQ
EXTERNAL VEHICLE SLAB	+ 80	20	N32	(1)

- DENOTES SLUMP AT PLANT
- (1) DENOTES MAXIMUM BASE SHRINKAGE STRAIN 600 x 10 ⁻⁶ AT 56 DAYS (TO AS 1012 PART 13)
- C4. SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED
- C5. BEAM DEPTHS ARE WRITTEN FIRST AND INCLUDE SLAB THICKNESS, IF ANY.
- C6. HOLES, CHASES OR EMBEDMENT ITEMS, INCLUDING PIPES AND CONDUITS SHALL NOT BE PLACED IN CONCRETE MEMBERS WITHOUT PRIOR APPROVAL OF THE ENGINEER.
- C7. CONDUITS, PIPES AND LIKE SHALL NOT BE PLACED WITHIN THE CONCRETE COVER, NOR DISPLACE THE REINFORCEMENT LAYERS.
- C8. CONSTRUCTION JOINTS (CJ) SHALL BE PROPERLY FORMED AND USED ONLY WHERE SHOWN OR SPECIFICALLY APPROVED BY THE ENGINEER. ALL CONSTRUCTION JOINTS SHALL BE THOROUGHLY SCABBLED.
- C9. THE MAXIMUM HEIGHT OF POUR FOR CONCRETE ELEMENTS SHALL BE 3m UNLESS METHOD OF PLACEMENT HAS BEEN APPROVED BY THE ENGINEER. COLUMNS SHALL NOT BE POURED WITH THE SLAB OVER.
- C10. CONCRETE SHALL BE THOROUGHLY COMPACTED IN THE FORMS BY MEANS OF MECHANICAL VIBRATION.
- C11. WHEN THE SHADE TEMPERATURE EXCEEDS 35°C, THE EXPOSED SURFACE OF CONCRETE SHALL BE SPRAYED WITH A FINE FILM OF APPROVED ALIPHATIC ALCOHOL DURING CONCRETE PLACEMENT AND FINISHING IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. ENSURING ADEQUATE SUPPLY OF ALIPHATIC ALCOHOL ON SITE BEFORE COMMENCING CONCRETE WORK.
- C12. CURING OF CONCRETE SHALL COMMENCE WITHIN 2 HOURS OF FINISHING OPERATIONS AND SHALL BE MAINTAINED FOR A MINIMUM OF 7 DAYS USING AN APPROVED PROPRIETARY CURING COMPOUND IN ACCORDANCE WITH AS 3799 AND COMPATIBLE WITH THE PROPOSED FINISH OR CONTINUOUS PONDING WITH POTABLE WATER.

 THE CONTRACTOR TO SUBMIT PROPOSED CURING PROCEDURE FOR
- C13. ALL CONCRETE DELIVERED TO SITE SHALL BE SUBJECT TO PROJECT ASSESSMENT IN ACCORDANCE WITH AS 1379.

APPROVAL OF THE ENGINEER.

C14. THE CONTRACTOR SHALL NOMINATE A CONCRETE DELIVERY SUPERVISOR WHO SHALL BE A SUITABLE EXPERIENCED PERSON FOR THE APPROVAL OF THE ENGINEER, TO MONITOR THE DELIVERY AND PLACING OF THE CONCRETE FOR EACH POUR ON THE PROJECT. IN ADDITION, THE MANUFACTURER SHALL SAMPLE AND TEST FOR DRYING SHRINKAGE EACH TYPE OF CONCRETE SUPPLIED, AT LEAST EVERY MONTH DURING THE COURSE OF THE PROJECT OR FOR EVERY 1000 CUBIC METRES PLACED. NATA TEST CERTIFICATES SHALL BE FORWARDED TO THE ENGINEER. THE RESULTS OF THESE TESTS SHALL ALSO BE KEPT ON SITE.

C15. CONCRETE SAMPLES AND TESTS

ARRANGE FOR A NATA REGISTERED TESTING LABORATORY TO TAKE SAMPLES OF AND TEST CONCRETE FOR COMPRESSION, FLEXURAL TENSILE STRENGTH (SLABS ON GROUND ONLY) AND SLUMP.

COMPRESSION TEST SAMPLES SHALL CONSIST OF 3 STANDARD CYLINDERS (4 STANDARD CYLINDERS FOR POST-TENSIONED CONCRETE), TESTED FOR COMPRESSIVE STRENGTH AS FOLLOWS:

ONE (1) CYLINDER AT 7 DAYS. TWO (2) CYLINDERS AT 28 DAYS.

ONE (1) CYLINDER AT 3 DAYS FOR POST-TENSIONED CONCRETE ONLY.

1 SAMPLE PER TRUCK AT TIME OF POURING.

THE MINIMUM NUMBER OF DAILY SAMPLES SHALL BE AS FOLLOWS:

IN COLUMNS/WALLS: 1 SAMPLE PER TRUCK

6 TO 10 TRUCKS PER DAY - 3 SAMPLES

10 TO 20 TRUCKS PER DAY - 4 SAMPLES

ALL OTHER CONCRETE OF ANY ONE TYPE AS FOLLOWS:

1 TRUCK PER DAY

- 1 SAMPLE

2 TO 5 TRUCKS PER DAY

- 2 SAMPLES

FOR EACH ADDITIONAL 10 TRUCKS PER DAY, 1 SAMPLE.

C16. REFER TO TYPICAL STRIPPING AND PROPPING DETAIL.

B NOTE D8 ADDED

A ISSUED FOR APPROVAL

MP 26/06/24

MP 15/04/24

REVISION DESCRIPTION





COPYRIGHT
THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER
(QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT
THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD.
DISCLAIMER
THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY
GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE
PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD)
PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY
CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR
OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS
BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR
ELECTRONICALLY BY ANY THIRD PARTY.
NOTE
THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION
PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE
PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE
DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITI
OR OFF-SITE WORKS OR FABRICATION.
IF IN DOUBT - ASK.

PARK LAKE ADARE PTY LTD
PO BOX 4107 SPRINGFIELD QLD 4300

PROPOSED SUBDIVISION

174 ADARE ROAD, ADARE, QLD 4343

STAGES 4 AND 5

STANDARD NOTES

FOR APPROVAL

NOT TO BE USED FOR CONSTRUCTION

PROJECT LEADER CK

DESIGNER MP

SIGNATURE

MP

SCALE DATE SHEET SIZE

MP


AS SHOWN 15/04/24


A1

C4001

BR242001

EVISION






	CONTROL LINE SETOUT - BUSHFIRE TRAIL 3										
PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE				
IP 1	0.000	430132.890	6955032.804	49°48'52.57"							
TC	10.985	430141.282	6955039.893	49°48'52.57"							
IP 2	14.390	430144.053	6955042.232		R = 8.000	6.809	48°45'53.94"				
СТ	17.794	430147.638	6955041.692	98°34'46.51"							
IP 3	262.984	430390.084	6955005.113								
IP 4	401.652	430488.313	6954907.236								
IP 5	478.299	430548.398	6954859.649								
IP 6	585.818	430550.741	6954752.155								
IP 7	666.750	430479.117	6954714.472								
IP 8	699.139	430449.198	6954726.875								
IP 9	712.841	430439.633	6954717.063								
IP 10	725.073	430428.891	6954711.213								
IP 11	764.170	430390.610	6954703.265								
IP 12	788.089	430366.780	6954701.205								
IP 13	798.958	430355.949	6954700.301								
IP 14	815.864	430347.573	6954714.986	330°18'00.00"							

	CONTROL LINE SETOUT - BUSHFIRE TRAIL 4										
PT	CHAINAGE	EASTING	NORTHING	BEARING							
IP 1	0.000	430410.978	6954862.144	67°51'20.12"							
IP 2	95.758	430499.672	6954898.239	67°51'20.12"	_						

REVIS	IONS:		
	IOOUED FOR ADDROVAL	MD	45/04/04
A	ISSUED FOR APPROVAL	MP	15/04/24
No.	REVISION DESCRIPTION	DRAWN	DATE








g	COPYRIGHT THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOU THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD. DISCLAIMER THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD) PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR ELECTRONICALLY BY ANY THIRD PARTY.
au td 15	NOTE THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIEY DIMENSIONS PRIOR TO COMMENCING ANY ON-SIT OR OFF-SITE WORKS OR FABRICATION. IF IN DOUBT - ASK.

PROPERTY OF VAN DER MEER LED, COPIED OR USED WITHOUT D) PTY LTD. E ELECTRONICALLY MAY ONLY BE USED FOR THE NOED. VAN DER MEER (QLD) SILITY FOR ANY SE OF THE DRAWING FOR DR WHERE THE DRAWING HAS D EITHER MANUALLY OR						DARE ELD QLD 4	PTY LTD	
/. TISSUED FOR INFORMATION	SCALE							_
URED DIMENSIONS TAKE SCALE REDUCED SIZE	0	7.5	15	22.5	30	37.5m		
R TO COMMENCING ANY ON-SITE								
	SC	ALE 1:7	50					

PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343 STAGES 4 AND 5


PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343			PROVAL OR CONSTRUCT	ION
STAGES 4 AND 5	PROJECT LEADER CK	DESIGNER MP	SIGNATURE	GK.
SITE PLAN	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1
SHEET 2	JOB No. BR24200	_	C4003	REVISION




		NITOOL	INIE OFTO		·DOENIOV A	00500							
	CONTROL LINE SETOUT - EMERGENCY ACCESS												
PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE						
IP 1	0.000	430132.890	6955032.804	49°48'52.57"									
TC	10.985	430141.282	6955039.893	49°48'52.57"									
IP 2	14.390	430144.053	6955042.232		R = 8.000	6.809	48°45'53.94"						
СТ	17.794	430147.638	6955041.692	98°34'46.51"									
IP 3	262.984	430390.084	6955005.113										
IP 4	401.652	430488.313	6954907.236										
IP 5	478.299	430548.398	6954859.649										
IP 6	585.818	430550.741	6954752.155										
IP 7	666.750	430479.117	6954714.472										
IP 8	699.139	430449.198	6954726.875										
IP 9	712.841	430439.633	6954717.063										
IP 10	725.073	430428.891	6954711.213										
IP 11	764.170	430390.610	6954703.265										
IP 12	788.089	430366.780	6954701.205										
IP 13	798.958	430355.949	6954700.301										
IP 14	815.864	430347.573	6954714.986	330°18'00.00"		_							

		CONTRO	L LINE SE	TOUT - BI	JSHFIRE T	RAIL 5	
PT	CHAINAGE	EASTING	NORTHING	BEARING	RAD/SPIRAL	A.LENGTH	DEFL.ANGLE
IP 1	0.000	430141.870	6954845.000	264°17'49.22"			
TC	6.365	430135.536	6954844.367	264°17'49.22"			
IP 2	8.736	430133.131	6954844.127		R = 10.000	4.742	27°10'10.78"
СТ	11.107	430130.882	6954845.011	291°28'00.00"			
IP 3	16.114	430126.224	6954846.843				
IP 4	82.169	430064.621	6954870.686				
IP 5	209.918	429944.088	6954913.014				
IP 6	350.579	429805.957	6954939.572				
IP 7	643.216	429513.324	6954940.941				
IP8	651.458	429505.195	6954942.301				
IP 9	659.720	429497.621	6954945.602				
IP 10	732.210	429436.170	6954984.056				
TC	802.857	429371.770	6955013.100	294°16'30.00"			
IP 11	805.319	429369.479	6955014.133		R = -10.000	4.924	28°12'42.51"
СТ	807.781	429366.972	6955013.961	266°03'47.49"			
IP 12	835.117	429339.700	6955012.084	266°03'47.49"			

CONTROL LINE SETOUT - BUSHFIRE TRAIL 6									
PT	CHAINAGE	EASTING	NORTHING	BEARING					
IP 1	0.000	429710.341	6955102.588	188°34'47.00"					
IP 2	164.292	429685.831	6954940.134	188°34'47.00"					










_	COPYRIGHT THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD. DISCLAIMER	
,	THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD) PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY	
ı	CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR	
i d	ELECTRONICALLY BY ANY THIRD PARTY. NOTE THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION. IF IN DOLIBY T. ASK.	


CLIENT	
PARK LAKE ADARE PTY LTD)
PO BOX 4107 SPRINGFIELD QLD 4300	


								STAGES 4 AND 5
SC	CALE							DRAWING TITLE
	0	7.5	15	22.5	30	37.5m	75m	SITE PLAN
	SCAL	E 1:75	50					SHEET 3


PROJECT TITLE	
PROPOSE	D SUBDIVISION
	, ADARE, QLD 4343
STAGES 4 AND 5	

NOT	FOR API	PROVAL OR CONSTRUCT	ION
PROJECT LEADER CK	DESIGNER MP	SIGNATURE	ak
DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1
JOB No. BR24200		C4004	REVISION












TYPICAL INSTALLATION OF A SEDIMENT FENCE NOT TO SCALE






CONSTRUCTION ENTRY/EXIT POINT DETAIL NOT TO SCALE



TOP OF BUND 1.5m

SEDIMENT BASIN EMERGENCY SPILLWAY DETAIL



ON-GRADE KERB INLET SEDIMENT TRAP

4.0 m (min)

1 m (max) on public roads

Filter socks overlap

NOT TO SCALE


onto kerb \

Sediment


pond

Run-off

SAG INLET SEDIMENT TRAP NOT TO SCALE




STOCKPILE SEDIMENT CONTROL NOT TO SCALE



SINGLE LAYER OF SANDBAGS TO FORM A V SHAPE WEIR IN-CHANNEL. PLACE IS SUCH A MANNER AS TO NOT DISPLACE STORMWATER RUNOFF OUTSIDE OF SWALE I.E. CENTRE OF WEIR MUST BE LOWER THAN SURROUNDING SURFACE

TYPICAL SAND BAG CHECK DAM NOT TO SCALE



FIELD INLET SEDIMENT TRAP NOT TO SCALE

REVISIONS:

REVISION DESCRIPTION





NOT TO SCALE

DN75, 300 THICK DUMPED ROCK SCOUR -

PROTECTION OVER GEOFABRIC TO

EMERGENCY SPILLWAY

g	COPYRIGHT THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD. DISCLAIMER	С
ອ	THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD) PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY	
	CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSSE OR WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR ELECTRONICALLY BY ANY THIRD PARTY. NOTE	S
au td 15	THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION. IF IN DOUBT - ASK.	

CLIENT
PARK LAKE ADARE PTY LTD
PO BOX 4107 SPRINGFIELD QLD 4300

-DN75, 300 THICK DUMPED ROCK SCOUR

PROTECTION OVER GEOFABRIC TO

EMERGENCY SPILLWAY

PROJECT TITLE
PROPOSED SUBDIVISION
174 ADARE ROAD, ADARE, QLD 4343
STAGES 4 AND 5
DRAWING TITLE

PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343	DRAWING STATUS		PROVAL OR CONSTRUCT	TION
STAGES 4 AND 5	PROJECT LEADER CK	DESIGNER MP	SIGNATURE	4
EROSION AND SEDIMENT	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZ
CONTROL DETAILS	JOB No. BR24200		CA190	REVISION

SEDIMENT FENCE

MATERIALS

- 1. FABRIC: POLYPROPYLENE, POLYAMIDE, NYLON, POLYESTER OR POLYETHYLENE WOVEN OR NON-WOVEN FABRIC, AT LEAST 700mm IN WIDTH AND A MINIMUM UNIT WEIGHT OF 140GSM.
- 2. SUPPORT POSTS/STAKES AND STEEL STAR PICKETS SUITABLE FOR ATTACHING FABRIC.

INSTALLATION

- 1. WHERE POSSIBLE INSTALL SEDIMENT FENCE AT LEAST 2m FROM THE TOE OF ANY FILLING OPERATIONS THAT MAY RESULT IN SHIFTING SOIL/FILL DAMAGING THE FENCE.
- 2. ENSURE THE EXTREME ENDS OF THE FENCE ARE TURNED UP THE SLOPE AT LEAST 1.5m OR AS NECESSARY TO MINIMISE WATER BYPASSING AROUND THE FENCE.
- 3. ENSURE THE SEDIMENT FENCE IS INSTALLED IN A MANNER THAT AVOIDS THE CONCENTRATION OF FLOW ALONG THE FENCE AND THE UNDESIRABLE DISCHARGE OF WATER AROUND THE ENDS OF THE FENCE.
- 4. IF THE SEDIMENT FENCE IS TO BE INSTALLED ALONG THE EDGE OF THE EXISTING TREES, ENSURE CARE IS TAKEN TO PROTECT THE TREES AND THEIR ROOT SYSTEMS DURING INSTALLATION OF THE FENCE.
- 5. UNLESS DIRECTED BY THE SITE SUPERVISOR OR THE APPROVED PLANS, EXCAVATE A 200mm WIDE BY 200mm DEEP TRENCH ALONG THE PROPOSED FENCE LINE, PLACING THE EXCAVATED MATERIAL ON THE UP-SLOPE SIDE OF THE TRENCH.
- 6. ALONG THE LOWER SIDE OF THE TRENCH, APPROPRIATELY SECURE THE STAKES INTO THE GROUND SPACED NO GREATER THAN 3m IF SUPPORTED BY A TOP SUPPORT WIRE OR WEIR MESH BACKING, OTHERWISE NO GREATER THAN 2m.
- 7. WHEREVER POSSIBLE, CONSTRUCT THE SEDIMENT FENCE FROM A CONTINUOUS ROLL OF FABRIC. TO JOIN FABRIC ATTACH EACH END OF TWO OVERLAPPING STAKES WITH THE FABRIC FOLDING AROUND THE ASSOCIATED STAKE ONE TURN AND WITH TWO STAKES TIED TOGETHER WITH THE WIRE METHOD OR OVERLAP THE FABRIC TO THE NEXT ADJACENT SUPPORT POST.
- 8. SECURELY ATTACH THE FABRIC TO THE SUPPORT POSTS USING 25 X 12.5mm STAPLES, OR TIE WIRE AT MAXIMUM 150mm SPACING.
- 9. SECURELY ATTACH THE FABRIC TO THE SUPPORT WIRE/MESH (IF ANY) AT A MAXIMUM SPACING
- 10. ENSURE THE COMPLETED SEDIMENT FENCE IS AT LEAST 450mm, BUT NOT MORE THAN 700mm HIGH. IF A SPILL THROUGH WEIR IS INSTALLED, ENSURE THE CREST OF THE WEIR IS AT LEAST 300mm ABOVE GROUND LEVEL.
- 11. BACKFILL THE TRENCH AND TAMP THE FILL TO FIRMLY ANCHOR THE BOTTOM OF THE FABRIC AND MESH TO PREVENT WATER FROM FLOWING UNDER THE FENCE.
- 12. IF IT IS NOT POSSIBLE TO ANCHOR THE FABRIC IN AN EXCAVATED TRENCH, THEN USE A CONTINUOUS LAYER OF SAND OR AGGREGATE TO HOLD THE FABRIC FIRMLY ON THE GROUND.

MAINTENANCE

- 1. INSPECT THE SEDIMENT FENCE AT LEAST WEEKLY AND AFTER ANY SIGNIFICANT RAIN. MAKE NECESSARY REPAIRS IMMEDIATELY.
- 2. REPAIR ANY TORN SECTIONS WITH A CONTINUOUS PIECE OF FABRIC FROM POST TO POST.
- 3. WHEN MAKING REPAIRS, ALWAYS RESTORE THE SYSTEM TO ITS ORIGINAL CONFIGURATION UNLESS AN AMENDED LAYOUT IS REQUIRED OR SPECIFIED.
- 4. IF THE FENCE IS SAGGING BETWEEN STAKES, INSTALL ADDITIONAL SUPPORT POSTS.
- 5. REMOVE ACCUMULATED SEDIMENT IF THE SEDIMENT DEPOSIT EXCEEDS A DEPTH OF 1/3 THE
- 6. DISPOSE OF SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.

SEDIMENT BASINS

GENERAL

- 1. SEDIMENT BASIN TO BE LOCATED ABOVE THE 5YR FLOOD LINE. INSTALL SEDIMENT BASINS FOR ALL CATCHMENTS ACROSS THE PROJECT AREA.
- 2. MATERIALS USED IN THE CONSTRUCTION OF SEDIMENT BASINS SHOULD NOT HAVE AN EMERSON NUMBER OF 3 OR ABOVE (I.E. DISPERSIVE SOILS SUCH AS THE SUBSOILS THAT CAN BE ENCOUNTERED AT THE SITE CANNOT BE USED TO CONSTRUCT SEDIMENT BASINS).
- 3. A "FULL OF SEDIMENT" MARKER MUST BE PLACED IN THE SEDIMENT BASIN TO SHOW THE DESIGN DEPTH OF THE SOIL/STORAGE ZONE VOLUME AND TO INDICATE WHEN REMOVAL OF THE SEDIMENT IS TO BE CARRIED OUT
- 4. CONSTRUCTED SEDIMENT BASINS TO BE FULLY OPERATIONAL THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL THE BASINS CATCHMENT AREA ACHIEVES 70% GROUND COVER ON ALL SOIL SURFACES.
- 5. FLOCCULATION REQUIREMENTS TO BE IN ACCORDANCE WITH TABLE B17 OF THE IECA GUIDELINES. IN GENERAL 32kg OF GYPSUM TO BE ADDED TO 100m3 OF STORED WATER.

MAINTENANCE

- 1. INSPECT THE SEDIMENT BASIN DURING THE FOLLOWING PERIODS AS STATED WITHIN PAGE B.52 OF THE IECA GUIDELINES:
- 1.1. DURING CONSTRUCTION TO DETERMINE WHETHER MACHINERY, FALLING TREES OR CONSTRUCTION ACTIVITY HAS DAMAGED ANY COMPONENT OF THE SEDIMENT BASIN. IF DAMAGE HAS OCCURRED, REPAIR IT.
- 1.2. AFTER EACH RUNOFF EVENT. INSPECT THE EROSION DAMAGE AT FLOW ENTRY AND EXIT POINTS. IF DAMAGE HAS OCCURRED, MAKE THE NECESSARY REPAIRS.
- 1.3. AT LEAST WEEKLY DURING THE NOMINATED WET SEASON (IF ANY) OTHERWISE AT LEAST FORTNIGHTLY.
- 1.4. PRIOR TO, AND IMMEDIATELY AFTER, PERIODS OF "STOP WORK" OR SITE "SHUTDOWN"
- 2. CLEAN OUT ACCUMULATED SEDIMENT WHEN IT REACHES THE MARKER BOARD/POST, AND RESTORE THE ORIGINAL STORAGE VOLUME. PLACE SEDIMENT IN A DISPOSAL AREA OR, IF APPROPRIATE, MIX WITH DRY SOIL ON THE SITE.
- 3. DO NOT DISPOSE OF SEDIMENT IN A MANNER THAT WILL CREATE AN EROSION OR POLLUTION HAZARD.
- 4. CHECK ALL VISIBLE PIPE CONNECTIONS FOR LEAKS, AND REPAIR AS NECESSARY.
- 5. CHECK FILL MATERIAL IN THE DAM FOR EXCESSIVE SETTLEMENT, SLUMPING OF THE SLOPES OR PIPING BETWEEN THE CONDUIT AND THE EMBANKMENT; MAKE ALL NECESSARY REPAIRS.
- 6. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE BASIN AND RISER.
- 7. SUBMERGED INFLOW PIPES MUST BE INSPECTED AND DE-SILTED (AS REQUIRED) AFTER EACH INFLOW EVENT.

REMOVAL OR CONVERSION OF SEDIMENT BASIN

- 1. WHEN GRADING AND CONSTRUCTION IN THE DRAINAGE AREA ABOVE A TEMPORARY SEDIMENT BASIN IS COMPLETED AND THE DISTURBED AREAS ARE ADEQUATELY STABILISED, THE BASIN MUST BE REMOVED OR OTHERWISE INCORPORATED INTO THE PERMANENT STORMWATER DRAINAGE SYSTEM. IN EITHER CASE, SEDIMENT SHOULD BE CLEARED AND PROPERLY DISPOSED OF AND THE BASIN AREA STABILISED
- 2. BEFORE STARTING ANY MAINTENANCE WORK ON THE BASIN OR SPILLWAY, INSTALL ALL NECESSARY SHORT-TERM SEDIMENT CONTROL MEASURES DOWNSTREAM OF THE SEDIMENT
- 3. ALL WATER AND SEDIMENT MUST BE REMOVED FROM THE BASIN PRIOR TO THE DAM'S REMOVAL. DISPOSE OF SEDIMENT AND WATER IN A MANNER THAT WILL NOT CREATE AN **EROSION OR POLLUTION HAZARD**
- 4. BRING THE DISTURBED AREA TO A PROPER GRADE, THEN SMOOTH, COMPACT AND STABILISE OR REVEGETATE AS REQUIRED TO ESTABLISH A STABLE LAND SURFACE.

MATERIAL STOCKPILING:

- 1. THE CONSTRUCTION CONTRACTOR IS TO ADHERE TO THE FOLLOWING SOIL AND STOCKPILE MANAGEMENT PRACTISES. STOCKPILES OF ERODIBLE MATERIAL THAT HAS THE POTENTIAL TO CAUSE ENVIRONMENTAL HARM IF DISPLACED MUST BE:
- 2. APPROPRIATELY PROTECTED FROM WIND, RAIN, CONCENTRATED SURFACE FLOW AND EXCESSIVE UP-SLOPE STORMWATER SURFACE FLOWS.
- 3. LOCATED AT LEAST 2m FROM ANY HAZARDOUS AREA, RETAINED VEGETATION, OR CONCENTRATED DRAINAGE LINE.
- 4. LOCATED UP-SLOPE OF AN APPROPRIATE SEDIMENT CONTROL SYSTEM.
- 5. PROVIDED WITH AN APPROPRIATE PROTECTIVE COVER (SYNTHETIC, MULCH OR VEGETATIVE) IF THE MATERIALS ARE LIKELY TO BE STOCKPILED FOR MORE THAN 28 DAYS.
- 6. PROVIDED WITH AN APPROPRIATE PROTECTIVE COVER (SYNTHETIC, MULCH OR VEGETATIVE) IF THE MATERIALS ARE LIKELY TO BE STOCKPILED FOR MORE THAN 10 DAYS DURING THOSE MONTHS THAT HAVE A HIGH EROSION RISK.
- 7. PROVIDED WITH AN APPROPRIATE PROTECTIVE COVER (SYNTHETIC, MULCH OR VEGETATIVE) IF THE MATERIALS ARE LIKELY TO BE STOCKPILED FOR MORE THAN 5 DAYS DURING THOSE MONTHS THAT HAVE A HIGH EROSION RISK.
- 8. A SUITABLE FLOW DIVERSION SYSTEM MUST BE ESTABLISHED IMMEDIATELY UP-SLOPE OF A STOCKPILE OF ERODIBLE MATERIAL THAT HAS THE POTENTIAL TO CAUSE ENVIRONMENTAL HARM IF DISPLACED, IF THE UP-SLOPE CATCHMENT AREA DRAINING TO THE STOCKPILE EXCEEDS 1500m2.

STABILISED ENTRY/EXIT NOTES

MATERIALS

- ROCK: WELL GRADED, HARD, ANGULAR, EROSION RESISTANT ROCK, NOMINAL DIAMETER OF 50mm TO 75mm (SMALL DISTURBANCES) OR 100 TO 150mm (LARGE DISTURBANCES). ALL REASONABLE MEASURES MUST BE TAKEN TO OBTAIN ROCK OF NEAR UNIFORM SIZE.
- FOOTPATH STABILISING AGGREGATE: 25 TO 50mm GRAVEL OR AGGREGATE.
- GEOTEXTILE FABRIC: HEAVY-DUTY, NEEDLE-PUNCHED, NON-WOVEN FILTER CLOTH ('BIDIM' A24 OR EQUIVALENT).

- 1. REFER TO APPROVED PLANS FOR LOCATION AND DIMENSIONAL DETAILS. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION, DIMENSIONS, OR METHOD OF INSTALLATION, CONTACT THE ENGINEER OR RESPONSIBLE ON-SITE OFFICER
- 2. CLEAR THE LOCATION OF THE VIBRATION GRID, REMOVING STUMPS, ROOTS AND OTHER VEGETATION TO PROVIDE A FIRM FOUNDATION SO THAT THE ROCK IS NOT PRESSED INTO SOFT GROUND. CLEAR SUFFICIENT WIDTH TO ALLOW PASSAGE OF LARGE VEHICLES, BUT CLEAR ONLY THAT NECESSARY FOR THE EXIT. DO NOT CLEAR ADJACENT AREAS UNTIL THE REQUIRED EROSION AND SEDIMENT CONTROL DEVICES ARE IN PLACE
- 3. IF THE EXPOSED SOIL IS SOFT, PLASTIC OR CLAYEY, PLACE A SUB-BASE OF CRUSHED ROCK OR A LAYER OF HEAVY-DUTY FILTER CLOTH TO PROVIDE A FIRM FOUNDATION.
- 4. ENSURE THAT THE INSTALLATION OF THE VIBRATION GRID INCLUDES ADEQUATE SEDIMENT STORAGE VOLUME UNDER THE GRID. WHERE NECESSARY, INSTALL SUITABLE PRECAST SEDIMENT COLLECTION CHAMBERS
- 5. PLACE A ROCK PAD/RAMP FORMING A MINIMUM 200mm THICK LAYER OF CLEAN, OPEN-VOID ROCK OVER THE ROADWAY BETWEEN THE VIBRATION GRID AND THE SEALED STREET TO PREVENT TYRES FROM PICKING UP MORE SOIL AFTER THEY HAVE BEEN CLEANED.
- 6. IF THE ASSOCIATED CONSTRUCTION SITE IS UP-SLOPE OF THE ROCK PAD, THUS CAUSING STORMWATER RUNOFF TO FLOW TOWARDS THE ROCK PAD. THEN FORM A MINIMUM 300mm HIGH FLOW CONTROL BERM ACROSS THE ROCK PAD TO DIVERT SUCH RUNOFF TO A SUITABLE SEDIMENT TRAP
- 7. THE TOTAL LENGTH OF THE VIBRATION GRIP AND ROCK RAMPS SHOULD BE AT LEAST 15m WHERE PRACTICABLE, AND AS WIDE AS THE FULL WIDTH OF THE ENTRY OR EXIT AND AT LEAST 3m. THE ROCK RAMP SHOULD COMMENCE AT THE EDGE OF THE OFF-SITE SEALED ROAD OR PAVEMENT
- 8. FLARE THE END OF THE ROCK PAD WHERE IT MEETS THE PAVEMENT SO THAT THE WHEELS OF TURNING VEHICLES DO NOT TRAVEL OVER UNPROTECTED SOIL.

- 1. INSPECT VIBRATION GRID PRIOR TO FORECAST RAIN, DAILY DURING EXTENDED PERIODS OF RAINFALL, AFTER SIGNIFICANT RUNOFF-PRODUCING RAINFALL. OR OTHERWISE AT FORTNIGHTLY INTERVALS
- 2. IF SAND, SOIL, SEDIMENT OR MUD IS TRACKED OR WASHED ONTO THE ADJACENT SEALED ROADWAY, THEN SUCH MATERIAL MUST BE PHYSICALLY REMOVED, FIRST USING A SQUARE-EDGED SHOVEL, AND THEN A STIFF-BRISTLED BROOM, AND THEN BY A MECHANICAL VACUUM UNIT, IF AVAILABLE.
- 3. IF NECESSARY FOR SAFETY REASONS, THE ROADWAY SHALL ONLY BE WASHED CLEAN AFTER ALL REASONABLE EFFORTS HAVE BEEN TAKEN TO SHOVEL AND SWEEP THE MATERIAL FROM THE ROADWAY.
- 4. WHEN THE VOIDS BETWEEN THE ROCK BECOMES FILLED WITH MATERIAL AND THE EFFECTIVENESS OF THE ROCK RAMPS ARE REDUCED TO A POINT WHERE SEDIMENT IS BEING TRACKED OFF THE SITE, A NEW 100mm LAYER OF ROCK MUST BE ADDED AND/OR THE ROCK PAD MUST BE EXTENDED.
- 5. ENSURE ANY ASSOCIATED DRAINAGE CONTROL MEASURES ARE MAINTAINED IN ACCORDANCE WITH THEIR DESIRED OPERATIONAL CONDITION.
- 6. DISPOSE OF SEDIMENT AND DEBRIS IN A MANNER THAT WILL NOT CREATE AN EROSION OR POLLUTION HAZARD.

CHECK DAM SEDIMENT TRAPS

INSTALLATION

- 1. REFER TO APPROVED PLANS FOR LOCATION AND INSTALLATION DETAILS. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION OR METHOD OF INSTALLATION CONTACT THE ENGINEER OR RESPONSIBLE ON-SITE OFFICER FOR ASSISTANCE.
- 2. PRIOR TO PLACEMENT OF THE SEDIMENT TRAP, ENSURE THE DRAINAGE CHANNEL IS DEEP ENOUGH TO PREVENT WATER BEING UNSAFELY DIVERTED OUT OF THE DRAIN ONCE THE CHECK DAMS ARE INSTALLED
- 3. LOCATE EACH CHECK DAM SEDIMENT TRAP AS DIRECTED WITHIN THE APPROVED PLANS, OR OTHERWISE AT SUCH A SPACING TO ACHIEVE THE REQUIRED SEDIMENT TRAPPING OUTCOMES.
- 4. IF THE CHECK DAMS ARE ALSO BEING USED TO CONTROL EROSION WITHIN THE DRAINAGE CHANNEL, THEN LOCATE EACH SUCCESSIVE CHECK DAM SUCH THAT THE CREST OF THE IMMEDIATE DOWNSTREAM DAM IS LEVEL WITH THE CHANNEL INVERT AT THE IMMEDIATE UPSTREAM CHECK DAM.
- 5. ENSURE SAND BAGS EXTEND UP THE CHANNEL BANKS (WHERE PRACTICAL) TO A LEVEL AT LEAST 100mm ABOVE THE CREST LEVEL OF THE CHECK DAM.

MAINTENANCE

- 1. INSPECT EACH CHECK DAM AND THE DRAINAGE CHANNEL AT LEAST WEEKLY AND AFTER RUNOFF-PRODUCING RAINFALL.
- 2. CORRECT ALL DAMAGE IMMEDIATELY. IF SIGNIFICANT EROSION OCCURS BETWEEN ANY OF THE CHECK DAMS, THEN CHECK THE SPACING OF THE DAMS AND WHERE NECESSARY INSTALL INTERMEDIATE CHECK DAMS OR A SUITABLE CHANNEL LINER.
- 3. CHECK FOR DISPLACEMENT OF THE CHECK DAMS.
- 4. CHECK FOR SOIL SCOUR AROUND THE ENDS OF EACH CHECK DAM. IF SUCH EROSION IS OCCURRING, CONSIDER EXTENDING THE WIDTH OF THE CHECK DAM TO AVOID SUCH PROBLEMS.
- 5. IF SEVERE SOIL EROSION OCCURS EITHER UNDER OR AROUND THE CHECK DAMS, THEN SEEK EXPERT ADVICE ON AN ALTERNATIVE TREATMENT MEASURE.
- 6. DE-SILT SEDIMENT TRAP IF THE SEDIMENT LEVEL EXCEEDS 1/3 THE CREST HEIGHT.
- 7. DISPOSE OF COLLECTED SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.

KERB INLET SEDIMENT TRAPS

FROM ICEA (INTERNATIONAL EROSION SEDIMENT ASSOCIATION) AUSTRALASIA STANDARD DRAWING ESC-03 (DEC 09).

MATERIALS

- 1. SOCKS: MINIMUM 200mm DIAMETER SYNTHETIC OR BIODEGRADABLE TUBES MANUFACTURED FROM NON-WOVEN OR COMPOSITE FABRIC SUITABLE FOR THE 'FILTRATION' OF COARSE SEDIMENTS.
- 2. FILL MATERIAL: STRAW, CANE MULCH, COMPOSITE MATERIAL (AS4454), COARSE SAND, OR CLEAN AGGREGATE.
- 3. STAKES: MINIMUM 25 x 25mm TIMBER.

INSTALLATION


MAXIMISED.

- 1. REFER TO APPROVED PLANS FOR LOCATION AND INSTALLATION DETAILS. IF THERE ARE QUESTIONS OR PROBLEMS WITH THE LOCATION, DIMENSIONS OR METHOD OF INSTALLATION CONTACT THE ENGINEER OR RESPONSIBLE ON-SITE OFFICER FOR ASSISTANCE.
- 2. ENSURE THE SOCKS ARE PLACED INDIVIDUALLY OR COLLECTIVELY (AS A SINGLE SEDIMENT TRAP) SUCH THAT:
- (i) LEAKAGE AROUND OR UNDER THE SOCKS IS MINIMISED
- (ii) ADJOINING SOCKS ARE TIGHTLY BUTTED OR OVERLAPPED AT LEAST 450mm. (iii) THE SURFACE AREA OF POTENTIAL WATER PONDING UP-SLOPE OF EACH SEDIMENT TRAP IS
- (iv) TO THE MAXIMUM DEGREE PRACTICAL, ALL SEDIMENT-LADEN WATER WILL PASS THROUGH THE FORMED POND BEFORE FLOWING OVER THE DOWN-SLOPE END OF THE SEDIMENT TRAP.
- 3. WHEN PLACED ACROSS THE INVERT OF MINOR DRAINS, ENSURE THE SOCKS ARE PLACED SUCH THAT (i) THE CREST OF THE DOWNSTREAM SOCK IS LEVEL WITH THE CHANNEL INVERT AT THE IMMEDIATE UPSTREAM SOCK (IF ANY);
- (ii) EACH SOCK EXTENDS UP THE CHANNEL BANKS SUCK THAT THE CREST OF THE SOCK AT ITS LOWEST POINT IS LOWER THAN GROUND LEVEL AT EITHER END OF THE SOCK.
- 4. IF STAKES ARE REQUIRED TO ANCHOR THE SOCKS, THEIR SPACING DOES NOT EXCEED 1.2m OR SIX TIMES THE SOCK DIAMETER (WHICHEVER IS THE LESSER). A MAXIMUM STAKE SPACING OF 0.3m APPLIES WHEN USED TO FORM CHECK DAMS.

MAINTENANCE

- 1. INSPECT ALL FILTER SOCKS PRIOR TO FORECAST RAIN, DAILY DURING EXTENDED PERIODS OF RAINFALL, AFTER SIGNIFICANT RUNOFF PRODUCING STORMS OR OTHERWISE AT WEEKLY INTERVALS.
- 2. REPAIR OR REPLACE DAMAGED SOCKS.
- 3. THE BULK OF THE SEDIMENT COLLECTED BEHIND THE FILTER SOCKS SHOULD BE REMOVED BY SHOVEL AFTER EACH STORM EVENT.
- 4. REMOVE COLLECTED SEDIMENT AND DISPOSE OF IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.

- 1. ALL SAND, SOIL, SEDIMENT OR MUD MUST BE PHYSICALLY REMOVED FROM SEALED SURFACES, FIRST USING A SQUARE-EDGED SHOVEL, AND THEN A STIFF-BRISTLED BROOM, AND THEN BY A MECHANICAL VACUUM UNIT, IF AVAILABLE.
- 2. IF NECESSARY FOR SAFETY REASONS, THE SEALED SURFACE SHALL ONLY BE WASHED CLEAN AFTER ALL REASONABLE EFFORTS HAVE BEEN TAKEN TO SHOVEL AND SWEEP THE MATERIAL FROM THE SURFACE.
- 3. DISPOSE OF COLLECTED SEDIMENT IN A SUITABLE MANNER THAT WILL NOT CAUSE AN EROSION OR POLLUTION HAZARD.
- 4. ALL SYNTHETIC (PLASTIC) MESH OR OTHER NON READILY BIODEGRADABLE MATERIAL MUST BE REMOVED FROM THE SITE ONCE THE SLOPE OR DRAIN IS STABILISED, OR THE SOCKS HAVE DETERIORATED TO A POINT WHERE THEY ARE NO LONGER PROVIDING THEIR INTENDED DRAINAGE OR SEDIMENT CONTROL FUNCTION.







COPYRIGHT
THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER
(QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOU'
THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD. NCES ARISING FROM THE USE OF THE DRAWING FOR HIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SIT OR OFF-SITE WORKS OR FABRICATION.
IF IN DOUBT - ASK.


PARK LAKE ADARE PTY LTD PO BOX 4107 SPRINGFIELD QLD 4300


PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343 STAGES 4 AND 5

CONTROL NOTES

FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION PROJECT LEADER MP

DRAFTSPERSON SHEET SIZE MP AS SHOWN | 15/04/24 A1 **EROSION AND SEDIMENT** BR242001 C4191





NOTE

- 1. REFER TO CIVIL SPECIFICATIONS ON DRAWING C4001 FOR SUBGRADE PREPARATION REQUIREMENTS.
- 2. THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE DOUGLAS PARTNERS GEOTECHNICAL REPORT: 93323.00.R.01.REV01 DATED 19TH FEB 2018.

3. DETAILED BULK EARTHWORKS MODELLING HAS

NOT BEEN UNDERTAKEN FOR PIPE TRENCHING

LEVEL 1 COMPACTION

ALL FILLING ON SITE TO BE LEVEL 1 COMPACTED FILL AS PER AS3798 UNLESS NOTED OTHERWISE.
ALL FILLING OF EXISTING DAMS WITHIN INDIVIDUAL LOTS TO BE LEVEL 1 COMPACTED


ALL FILLING OF EXISTING DAMS WITHIN INDIVIDUAL LOTS TO BE LEVEL 1 COMPACTED FILL AS PER AS3798 UNLESS NOTED OTHERWISE.

(NOTE TYPE 2 TESTING MAY ONLY BE USED FOR INDIVIDUAL RESIDENTIAL LOTS ONLY)

CUT FILL 0.00m - 0.25m 0.25m - 0.50m 0.50m - 1.000m 1.00m - 2.00m > 2.00m

	<u>EXISTING</u>
COMMUNICATIONS	C(*)
DRAINAGE (unknown dia.)	D(*)
DRAINAGE (known dia.) ELECTRICITY	E(*)
O/H ELECTRICITY & POLE	
GAS	G(*)
WATER MAIN	W(*)

(*) - DENOTES QUALITY LEVEL AS PER A.S. 5488-2013.



DRAWING STATUS

REVIS	IONS:		
В	ELECTRICAL PADS ADDED	MP	26/06/2
Α	ISSUED FOR APPROVAL	MP	15/04/2
No.	REVISION DESCRIPTION	DRAWN	DATE







Telephone +61 7 3021 6600

COPYRIGHT
THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER
(QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT
THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD.
DISCLAIMER
THES DRAWING AND ITS CONTENTS ARE ELECTRONICALLY
GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE
PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD)
PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY
CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR
OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS
BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR
ELECTRONICALLY BY ANY THIRD PARTY.
NOTE
THIS SAN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION
PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE
PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE
DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE
OR OFF-SITE WORKS OR FABRICATION.
IF IN DOUBT - ASK.

CLIENT
PARK LAKE ADARE PTY LTD
PO BOX 4107 SPRINGFIELD QLD 4300

PC	BOX	4107	SPRII	NGFI	ELD QLD 4300	
SCALE 0	7.5	15	22.5	30	37.5m	75m
	CALE 1:7					


PROJECT TITLE
PROPOSED SUBDIVISION
174 ADARE ROAD, ADARE, QLD 4343
STAGES 4 AND 5

BULK EARTHWORKS PLAN


SHEET 2

FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION							
PROJECT LEADER CK	DESIGNER MP	SIGNATURE	GK.				
DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1				
JOB No. BR24200	=	C4201	REVISION B				







TYPICAL ELECTRICAL PILLAR PROTECTION DETAIL SCALE 1:50








TYPICAL LIGHT POLE PROTECTION DETAIL



TYPICAL LIGHT POLE SECTION A SCALE 1:50







ıg	COPYRIGHT THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD. DISCLAIMER THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD) PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY
au Ltd :15	CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR ELECTRONICALLY BY ANY THIRD PARTY. NOTE THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED, FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION. IF IN DOUBT - ASK.


CLIENT
PARK LAKE ADARE PTY LTD
PO BOX 4107 SPRINGFIELD QLD 4300


SCALE 1:50


AKE ADARE PTY LTD 7 SPRINGFIELD QLD 4300			D	PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343 STAGES 4 AND 5		
2	2	4	5m	BULK EARTHWORKS DETAILS		
		4	<u> </u>	DULK EAKTHWUKKS DETAILS		

PROJECT TITLE

J	FOR APPROVAL							
	NOT TO BE USED FOR CONSTRUCTION							
	PROJECT LEADER CK	DESIGNER MP	SIGNATURE					
	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1				
	JOB No. BR24200	=	DRAWING No. C4290					
















TREE TO REMAIN

TREE TO BE REMOVED

PARK LAKE ADARE PTY LTD PO BOX 4107 SPRINGFIELD QLD 4300

7.5 15 22.5 30 ^{37.5m}

SCALE 1:750

PROPOSED 174 ADARE ROAD, STAGES 4 AND 5

REFER DRGS C4700-C1716 FOR DETAILS.

HEAVY DUTY DRIVEWAY

BUSHFIRE TRAIL

REFER IPWEA STD DRG RS-051

PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343	FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION			
STAGES 4 AND 5	PROJECT LEADER CK	designer MP	SIGNATURE	9
PAVEMENT PLAN	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET S A1
SHEET 2	JOB No. BR24200		C4301	REVISIO

PAVEMENT SHOULD BE LIMITED, AS PROLONGED USE WILL

THE PROPOSED WORK SHOULD BE CUT IN TO EXPOSE THE

EDGE OF THE EXISTING PAVEMENT AND NOT SIMPLY BUTTED


SHEET SIZE


A1


REVISION


RESULT IN A CONSIDERABLY REDUCED PAVEMENT LIFE.


AGAINST THE EDGE OF THE EXISTING SURFACE.















PAVEMENT MARKING LEGEND


- SEPARATION LINE UNBROKEN (150mm)
- LANE LINE BROKEN (150mm) 3m LINE, 9m GAP
- GWL GIVE WAY LINE (300mm)

SIGNS LEGEND



- ALL LONGITUDINAL LINES AS PER MUTCD SECTION 5.2.
- ALL TRANSVERSE LINES AS PER MUTCD SECTION 5.4. DIAGONAL AND CHEVRONS AS PER MUTCD SECTION 5.5.
- 4. ALL LINEWORK TO HAVE RAISED REFLECTIVE MARKERS
- INSTALLED AS PER MUTCD SECTION 5.6. PAINT FULL WIDTH EDGE LINE (EL) 200mm FROM EDGE OF
- BITUMEN AS SHOWN. INSTALL GUIDE POSTS TO EDGE OF BITUMEN ALONG TABLE.
- DRAINS IN ACCORDANCE WITH TMR STD DRG SD1356.
- INSTALL GUIDE POSTS TO BOTH SIDES OF ALL DRIVEWAYS.
- LINEMARKING SHALL BE DULUX ROADMASTER WATER
- BASED PAVEMENT MARKING OR APPROVED EQUIVALENT. GIVEWAY PAVEMENT MARKING LOCATIONS TO BE IN

ACCORDANCE WITH MUTCD.















SCALE						
0	7.5	15	22.5	30	37.5m	75m
SC	ALE 1:7	50				


PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343


STAGES 4 AND 5
DRAWING TITLE
SIGNS AND PAVEMENT
MARKING PLAN - SHEET 2

FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION DESIGNER MP PROJECT LEADER CK DRAFTSPERSON SHEET SIZE AS SHOWN | 15/04/24 MP A1 BR242001 C4431









THE AUTHORITY OF VAN DER MEER (QLD) PTY LID.

DISCLAIMER

THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY
GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE
PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD)
PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY
CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR
OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS
BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR
ELECTRONICALLY BY ANY THIRD PARTY.
NOTE

www.vandermeer.com.au an der Meer (QLD) Pty Ltd A.B.N. 63 609 812 615

NOTE THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWNINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION. IF IN DOUBT - ASK.

PO BOX 4107 SPRINGFIELD QLD 4300

174 ADARE ROAD, ADARE, QLD 4343

ROAD LONGITUDINAL SECTION

NEWLAND PLACE - SHEET 3

STAGES 4 AND 5

NOT TO BE USED FOR CONSTRUCTION

AS SHOWN | 15/04/24

C4452

SHEET SIZE

A1

DESIGNER MP

PROJECT LEADER

DRAFTSPERSON

BR242001

MP

van der Meer Consulting

van der Meer (QLD) Pty Ltd


FORTITUDE VALLEY QLD 4006

Telephone +61 7 3021 6600

ADARE

MP 15/04/24

REVISION DESCRIPTION



LONGITUDINAL SECTION - NEWLAND PLACE
HORIZONTAL SCALE 1:500

REVISIONS:

REVISIONS:


A ISSUED FOR APPROVAL
No. REVISION DESCRIPTION

No. REVISION DESCRIPTION

NO. DRAWN DATE







CLIENT
PARK LAKE ADARE PTY LTD
PO BOX 4107 SPRINGFIELD QLD 4300

I	PROJECT TITLE
	PROPOSED SUBDIVISION
	174 ADARE ROAD, ADARE, QLD 4343
	STAGES 4 AND 5
ļ	
	DRAWING TITLE

ROAD LONGITUDINAL SECTION


NEWLAND PLACE - SHEET 4


SCALE 1:500 (HORIZONTAL)


SCALE 1:50 (VE	RTICAL)		
DRAWING STATUS NOT	FOR API	PROVAL OR CONSTRUCT	ION
PROJECT LEADER CK	DESIGNER MP	SIGNATURE	ak
DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1
JOB No	Г	RAWING No.	REVISION


C4453


BR242001


























REVISIONS: ADARE MP 26/06/24 MP 15/04/24 DRAWN DATE B DIMENSIONS UPDATED
A ISSUED FOR APPROVAL REVISION DESCRIPTION





						RE P 7 QLD 4300	ΓY LTD	
SCALE								
0	1	2	3	4	5m			10m

SCALE 1:100


PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343		FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION			
	STAGES 4 AND 5	PROJECT LEADER CK	DESIGNER MP	SIGNATURE	6
	ROAD CROSS SECTIONS	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET S A1
	BURTON CRESCENT - SHEET 3	JOB No. BR24200	_	CA462	REVISIO


SHEET SIZE

A1

REVISION

В





LEGEND

<u>EXISTING</u>		PROPOSED		
	FENCE	$\longrightarrow \longrightarrow$	OPEN DRAIN	
\longrightarrow	OPEN DRAIN		MOUNTABLE KERB TYPE M4	
	MOUNTABLE KERB TYPE M4		MOUNTABLE KERB TYPE M6	
	MOUNTABLE KERB TYPE M6		CONTOUR (0.1m)	
<u> </u>	ROAD EDGE BITUMEN	<u> </u>	ROAD EDGE BITUMEN	
\bigcirc	TREE TO REMAIN		ROAD SHOULDER	
Ö	TREE TO BE REMOVED		DRAINAGE	

SERVICES (PUP) LEGEND

	<u>EXISTING</u>	PROPOSED
COMMUNICATIONS	C(*)	
DRAINAGE (unknown dia.)	D(*)	
DRAINAGE (known dia.) ELECTRICITY	E(*)	
O/H ELECTRICITY & POLE		
GAS	G(*)	
WATER MAIN	W(*)	w

(*) - DENOTES QUALITY LEVEL AS PER A.S. 5488-2013.

KERB LIP SETOUT / LEVELS

POINT	EASTING	NORTHING	LEVEL
1	430164.548	6954708.994	120.867
2	430165.305	6954712.842	120.993
3	430167.403	6954716.022	121.137
4	430170.422	6954718.135	121.268
5	430174.102	6954719.016	121.371
6	430173.084	6954724.976	121.534
7	430169.241	6954725.561	121.458
8	430165.833	6954727.639	121.410
9	430163.794	6954730.300	121.404
10	430162.676	6954734.106	121.449
11	430142.688	6954928.016	121.732
12	430143.502	6954932.097	121.780
13	430145.832	6954935.424	121.872
14	430149.086	6954937.472	121.921
15	430153.085	6954938.135	121.777
16	430152.080	6954944.172	121.654
17	430148.487	6954944.947	121.811
18	430145.364	6954947.020	121.895
19	430143.220	6954950.105	121.882
20	430142.358	6954954.041	121.888
21	430135.570	6955016.310	-999.000
22	430133.912	6955024.505	-999.000
23	430129.367	6955031.540	-999.000
24	430123.505	6955035.960	-999.000
25	430116.429	6955038.273	-999.000
26	429583.846	6955118.654	-999.000
27	429577.048	6955118.511	122.407
28	429571.379	6955116.487	122.362
29	429566.589	6955112.889	122.291
30	429560.719	6955110.210	122.270
31	429554.954	6955111.856	122.368
32	429551.630	6955116.342	122.499
33	429551.539	6955121.756	122.626
34	429554.933	6955126.515	122.739
35	429561.510	6955128.093	122.766
36	429567.779	6955127.147	122.696
37	429573.271	6955126.318	122.648
38	429578.826	6955125.479	122.618
39	429584.742	6955124.586	122.605

		31	
200	10	20	
NEWLAN 127.0	9	BURTON CRESCENT	
NEWLAND PLACE	8 7	\$ 0 6 E	
182.203 = 00		4 5 7374	
180	12 ₁ 0	1214	=
4.021 4.00.2 4.00.4	30.8		
1200		120 E	
	730.0		

REVIS	SIONS:		
С	CONTOURS UPDATED	MP	26/06/24
В	INFORMATION REQUEST RESPONSE	MP	09/05/24
Α	ISSUED FOR APPROVAL	MP	15/04/2
No.	REVISION DESCRIPTION	DRAWN	DATE







ng	COPYRIGHT THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD. DISCLAIMER THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD)
.au Ltd 515	PORTOSE FOR WILL NOT ACCEPT RESPONSIBILITY FOR ANY CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR ELECTRONICALLY BY ANY THIRD PARTY. NOTE THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED, FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION. IF IN DOUBT - ASK.


CLIENT
PARK LAKE ADARE PTY LTD
PO BOX 4107 SPRINGFIELD QLD 4300
PO BOX 4107 SPRINGFIELD QLD 4300

SCALE 1:200


PROJECT TITLE	
PROPOSED SUBDIVISION	
174 ADARE ROAD, ADARE, QLD 4343	
STAGES 4 AND 5	

INTERSECTION DETAILS


I	DRAWING STATUS	FOR API	PROVAL OR CONSTRUCT	ION
	PROJECT LEADER CK	DESIGNER MP	SIGNATURE	ak
	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1
	JOB No. BR24200	=	RAWING No. C4480	REVISION




SCALE 1:10




ROAD TYPICAL SECTION - NEWLAND PLACE - CH.403 TO END




ROAD TYPICAL SECTION - BURTON CRESCENT



ROAD TYPICAL SECTION - NEWLAND PLACE - CH.182 TO CH.403




ROAD TYPICAL SECTION - NEWLAND PLACE - CH.13.245 TO CH.182 SCALE 1:50









				D
1	2	3	4	5
50				
	X 4107 SF	X 4107 SPRINGFIEL	X 4107 SPRINGFIELD QLD 4300	K LAKE ADARE PTY LT K 4107 SPRINGFIELD QLD 4300

ROJECT TITLE
PROPOSED SUBDIVISION
174 ADARE ROAD, ADARE, QLD 4343
STAGES 4 AND 5
DAWING TITLE

ROADWORKS DETAILS


DRAWING STATUS	FOR API	PROVAL	
NOT	TO BE USED FO	OR CONSTRUCT	ION
PROJECT LEADER CK	DESIGNER MP	SIGNATURE	ak
DRAFTSPERSON MP	SCALE AS SHOWN	DATE 15/04/24	SHEET SIZE A1


SCALE 1:10


REFER DRAWING C4300 FOR


PAVEMENT TYPE LEGEND


REVISION BR242001 C4490 В


















	OCATION	W.		SI.	JB-CATCH!	MENT RU	NOEE											INLET DESIGN										DRAIN	DESIGN								ш	EAD LOSSES	ē.				PART FULL				DEST	GN LEVELS			
	LOCATION		Tc	_	Josephichi	-	CA	0	c	Qa								INCELDESION			Qg ((b	1	c 1	CA	Qra	at Q	_	S		Vf=Q/A	Qcap	Vcap Vt	t		Vf²/2g	77.02		Kw h	w s	hi	_	dn V		\equiv		UES	OIA FEATES			
STRUCTURE No.	CONTRIBUTING	DRAIN SECTION	SUB-CATCHMENT TIME OF CONC.	RAINFALL INTENSITY	CO-EFFICIENT OF RUNOFF	SUB-CATCHMENT AREA	EQUIVALENT AREA	SUB-CATCHMENT	DISCHARGE	BYPASS)	HALF ROAD CAPACITY	FLOW WIDTH	FLOW DEPTH	FLOW DxV		ROAD GRADE AT INLET	ROAD XFALL AT INLET	INLET TYPE	BLOCKAGE FACTOR	INLET CURVE	FLOW INTO INLET	WOALD COMPANY	DITASS SINCELORE NO.	RAINFALL INTENSITY	TOTAL (C×A)	PEAK FLOW	PIPE FLOW	REACHLENGTH	PIPEGRADE	PIPESIZE	FULL PIPE VELOCITY	CAPACITYFLOW	CAPACITY VELOCITY TRAVEL VELOCITY		CHART(S) USED	VELOCITY HEAD	U/S HEAD LOSS COEFFICIENT	U/S HEAD LOSS	W.S.E COEFFICIENT	PIPE FRICTION SLOPE	PIPE FRICTION HEAD	\$501	NORMAL DEPTH	T.F.S.L.	T15/Q 3010	PIPE U/S H.G.L	PIPE D/S H.G.L	W.S.E	SURFACELEVEL	FREEBOARD	STRUCTURE No.
			min	mm/h		ha	ha	Ų	s	L/s	L/s	m	m	m^2/	/s	%	%				L/s L	/s	m	in mm/	r ha	V	s L/s	m	%	mm	m/s	L/s	m/s m/	/s		m		m		n %	m	1	m m	/s m	m	n m	m	m	m	-	-
HW1/40 HW1/	1/40 HW	V1/40 to HW2/40	11.59986	140.6406	0.6	1.0779	0.6467	91 252.6	5808 25	2.6808						24	4.99979	CONCRETE HEADWALL	0.8	25	2.6808		11.5	9986 140.64	06 0.6467	791 252.6	808 252.68	8 14.40244	2.742592	450	1.588757	472.3583 2	.970001 2	Inlet	t Control 0	0.128783 2.	107014 0	.271348	0.27	1348 2.072	329 0.351	1059 0.2	34275 3.01	093 113.4	9 113.0)95 113.84	435 113.5	15 114.11	48 114.24	0.125187	HW1/40
HW2/40 HW2/	2/40																	CONCRETE HEADWALL																														113.54	45 113.745		HW2/40
FI1/41 FI1/4	/41 FI	11/41 to F12/41														21	1.01653	900 x 900 FIELD INLET	0.5				9	182		13	2 132	2.1	1.428571	(2x)225	1.659927	107.3805 1	350331 2	Outle	et Control 0	0.140579	1.5 0	.210869	0.21	0869 2.158	735 0.045	5333	0.225 1.65	/927 110./	6 110	57 111.40	057 111.36	03 111.61	65 112.7	1.083471	FI1/41
F12/41 F12/4	/41 F	12/41 to F13/41														21	1.01653	900 x 900 FIELD INLET	0.5				5.0	175 181.88	31	26	4 264	33.32074	0.417158	450	1.659927	184.2218 1	158314 2	Outle	et Control C	0.140579	1.5 0	.210869	0.21	0869 0.856	694 0.285	5457	0.45 1.65	927 110.5	5 110.	411 111.1/	495 110.8	54 111.360	03 112.7	1.339674	FI2/41
HW3/41 HW3/	3/41																	CONCRETE HEADWALL																														110.86	64 111.111		HW3/41
HW1/42 HW1/	1/42 HW	V1/42 to HW2/42	12.60378	136.0226	0.6	0.6400	0.3840	05 145.	1098 14	5.1098						32	2.14991	CONCRETE HEADWALL	0.8	14	5.1098		12.6	0378 136.02	26 0.384	05 145.1	098 145.10	8 7.2	3.611111	375	1.313846	333.32 3	.017929 2	Inlet	t Control 0	0.088071 2.	226044	0.19605	0.19	9605 2,303	955 0.214	1254 0.1	73084 2.91	2531 114.	3 114	04 114.58	809 114.4	15 114.770	69 114.99	0.213065	HW1/42
HW2/42 HW2/	2/42																	CONCRETE HEADWALL																														114.41	15 114.615		HW2/42
HW1/43 HW1/	1/43 HW	V1/43 to HW2/43	13.5817	131.5242	0.6	1.08749	9 0.6524	99 238.3	3874 23	8.3874						16	6,12072	CONCRETE HEADWALL	0.8	23	8.3874		13.5	817 131.52	42 0.6524	199 238.3	874 238.38	4 4.88	1.434426	600x300	1.324376	357,2736 1	.984855 2	Inlet	t Control 0	0.089488 2.	099846 0	187912	0.18	7912 0.462	074 0.059	9335 0.1	83558 2.16	4507 112.7	/6 112	.69 113.01	125 112.9	9 113.200	05 113.213	0.012539	HW1/43
HW2/43 HW2/	2/43																	CONCRETE HEADWALL																														112.99	9 113.215		HW2/43
HW1/44 HW1	1/44 HW	V1/44 to HW2/44	15.19497	124.3761	0.6	2.6364	1 1.5818	47 546.5	5108 54	6.5108						38	8.97055	CONCRETE HEADWALL	0.8	54	6.5108	_	15.1	9497 124.37	61 1.5818	347 546.5	108 546.51	8 7.20001	2.499996	2x)600x30	1.518087	943.3252 2	.620351 2	Inlet	t Control 0	0.117581 1.	912851 0	.224915	0.22	4915 1.13	488 0.102	2336 0.1	66193 2.74	0347 113.3	37 113	19 113.64	466 113.50	55 113.87	15 113.987	0.115474	HW1/44
HW2/44 HW2/	2/44									T								CONCRETE HEADWALL								\top																					1	113.56	65 113.865		HW2/44
HW1/45 HW1/	1/45 HW	/1/45 to HW2/45	14.65952	126.5662	0.6	0.4434	7 0.2660	82 93.54	719 93	.54719						35	5.85723	CONCRETE HEADWALL	0.8	93	54719		14.6	5952 126.56	62 0.2660	082 93.54	719 93.547	9 7.2	0.555556	375	0.84699	130.7389 1	.183729 2	Outle	et Control 0	0.036602 1.	584707 0	.058003	0.05	8003 0.221	046 0.017	7982 0.2	34682 1.28	5264 120.	5 120	.46 120.85	509 120.8	35 120.900	121.025	0.116082	HW1/45
HW2/45 HW2/	2/45																	CONCRETE HEADWALL				Ť																										120.83	35 120.985		HW2/45
HW1/46 HW1/	1/46 HW	/1/46 to HW2/46	14.65952	126.5662	0.6	0,0750	9 0.0450	29 15.8	3111 15	.83111	*					34	4.43696	CONCRETE HEADWALL	0.8	15	83111	1	14.6	5952 126.56	62 0.0450	29 15.83	111 15.831	1 7.2	1.305556	375	0.143337	200.4189 1	.814622 2	Outle	et Control 0	0.001048 2.	328441 0	.002441	0.00	2441 -0.00	537 0,000	0193 0,0	071298 1.08	2474 121.9	16 121	822 122.15	966 122.15	97 122.199	91 122.441	0.241946	HW1/46
HW2/46 HW2/	2/46						1											CONCRETE HEADWALL				1					1															\top			+			122.19	97 122.347		HW2/46
HW1/48 HW1/	1/48 HW	/1/48 to HW2/48	14.65952	126.5662	0.6	0.2714	5 0.1628	55 57.25	5548 57	.25548					T	55	9.59966	CONCRETE HEADWALL	0.8	57	.25548	1	14.6	5952 126.56	62 0.1628	855 57.25	548 57.255	8 7.2	2.222222	375	0.5184	261.4777 2	.367458 2	Outle	et Control 0	0.013711 1.	824345 0	.025014	0.02	5014 0.056	785 0.007	7053 0.1	19238 1.89	5727 119.3	38 119	.22 119.69	991 119.69	95 119.72	41 119.905	0.180898	HW1/48
HW2/48 HW2/	2/48							+										CONCRETE HEADWALL				+															1			\top							-	119.69	95 119.865		HW2/48
F11/49 F11/4	/49 HW	/1/49 to HW2/49	10.6047	145.2184	0.6	2.7479	2 1.6487	71 665.0	0885 66	5.0885			0.5966	546			25	900 x 900 FIELD INLET	0,5	66	5.0885		10.6	047 145.21	84 1.6487	771 665.0	885 665.08	5 15.08997	0.894634	600	2.352269	581.01 2	.054903 2	Inlet	t Control 0	0.282305 1	.69915 0	.479678	0.47	9678 1.177	295 0.176	6899	0.6 2.35	2269 118.7	45 118	.61 119.39	869 119.2	1 119.86	66 120.017	0.150423	F11/49
HW2/49 HW2/	2/49				-													CONCRETE HEADWALL												-															-			119.2	1 119.41		HW2/49
HW1/50 HW1/	1/50 HW	/1/50 to HW2/50	12.01722	138.7208	0.6	0.80818	6 0.4849	12 186.8	3537 18	6.8537					-	-3	3.98475	CONCRETE HEADWALL	0.8	18	6.8537		12.0	1722 138.72	08 0.4849	012 186.8	537 186.85	7 9.64	2.385892	375	1.691801	270.9358 2	.453093 2	Inlet	t Control	0.14603 2.0	087491 0	.304837	0.30	4837 1.769	189 0.205	5571 0.2	28971 2.64	4886 111.4	11 111	.18 111.7	256 111.59	55 112.030	04 112.035	0.004614	HW1/50
HW2/50 HW2/																		CONCRETE HEADWALL																														111.55	55 111.805		HW2/50
HW1/51 HW1/		/1/51 to HW2/51	14,65952	126.5662	0.6	0.1235	0.0741	31 26.0	623 20	6,0623	-				+	_		CONCRETE HEADWALL	0.8	20	5.0623	-	14.6	5952 126.56	62 0.0741	131 26.0	623 26.062	9.64009	4,668006	375	0.235972	378.9716	431265 2	Inlet	t Control 0	0.002841 12	2.21487 0	0.034702	0.03	4702 1.974	264 0.229	9145 0.0	066614 1.96	4847 127	121	55 122.1	153 121.9		5 122.525	-	
HW2/51 HW2/		and a nat I was the state of th	THE RESERVE		(4.0)				- TO 18	100 m					+	+	-	CONCRETE HEADWALL	(MAG)		ichet:	-		320.50	and the		2000000	100000000000000000000000000000000000000			200000000000000000000000000000000000000			, me	-andred			13 S. 10 S. 1	2022	-2.50	75.5	F. 100. 1933		a.en (2000)	-				25 122.075		HW2/51

STORMWATER CALCULATIONS TABLE (Q10)










PARK LAKE ADARE PTY LTD PO BOX 4107 SPRINGFIELD QLD 4300


PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343 STAGES 4 AND 5


FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION DESIGNER MP


DRAINAGE CALCULATIONS

PROJECT LEADER **CK** DRAFTSPERSON MP SHEET SIZE AS SHOWN | 15/04/24 A1 REVISION BR242001 C4560









REVISIONS:

A ISSUED FOR APPROVAL

No. REVISION DESCRIPTION

DRAWN DATE







PARK LAKE ADARE PTY LTD PO BOX 4107 SPRINGFIELD QLD 4300

PROPOSED SUBDIVISION
174 ADARE ROAD, ADARE, QLD 4343
STAGES 4 AND 5

SCALE 1:500 (HORIZONTAL)

50m

SCALE 1:50 (VE	RTICAL)		
DRAWING STATUS			
	FOR API	PROVAL	
NOT	TO BE USED FO	OR CONSTRUCT	ION
PROJECT LEADER CK	DESIGNER MP	SIGNATURE	GK.
DRAFTSPERSON	SCALE A C CLIONAINI	DATE 4.F.(O.4.(O.4.	SHEET SIZE

BUSHFIRE TRAIL 3 LONGITUDINAL SECTION - SHEET 3

CK
MP

RAFTSPERSON
MP

SCALE
AS SHOWN 15/04/24
A1


OB No.


DRAWING No.


C4703


A

REVISION
A









3% Datum RL.109.0 CH. 80.000 3% -3% Datum RL.110.0 CH. 60.000 3% -3% Datum RL.111.0 CH. 40.000 _EXISTING SURFACE 3% FINISHED SURFACE Datum RL.112.0 CH. 20.000

LONGITUDINAL SECTION - BUSHFIRE TRIAL 4

HORIZONTAL SCALE 1:500

VERTICAL SCALE 1:50

REVISIONS:

A ISSUED FOR APPROVAL

No. REVISION DESCRIPTION

MP 15/04/24

DRAWN DATE










R JT							RE PT\	/ LTD	
3									
	SCALE	1	2	3	1	5m			10m
TE		ı I		J	4				
	SC	ALE 1:1	00						

0 10 20 30 40 50 n	n 0 <u>1</u>	2	3	4 5m
SCALE 1:500 (HORIZONTAL)	SCALE 1:50 (V	ERTICAL)		
PROPOSED SUBDIVISION 174 ADARE ROAD, ADARE, QLD 4343	DRAWING STATUS	FOR AP		
STAGES 4 AND 5	PROJECT LEADER CK	designer MP	SIGNATURE	ak
BUSHFIRE TRAIL 4 LONGITUDINAL	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1
AND CROSS SECTIONS	JOB No. BR24200		C4707	REVISION







NOTE
THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION.

IF IN DOUBT - ASK.

www.vandermeer.com.au

A.B.N. 63 609 812 615

van der Meer (QLD) Pty Ltd

FORTITUDE VALLEY QLD 4006

Telephone +61 7 3021 6600

ADARE

MP 15/04/24

REVISION DESCRIPTION

DESIGNER MP

AS SHOWN | 15/04/24

C4710

SHEET SIZE

A1


PROJECT LEADER CK DRAFTSPERSON

BR242001

MP

BUSHFIRE TRAIL 5 LONGITUDINAL

SECTION - SHEET 2



REVISIONS:

A ISSUED FOR APPROVAL

No. REVISION DESCRIPTION

DRAWN DATE





COPYRIGHT
THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (QLD) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (QLD) PTY LTD. DISCLAIMER
THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (QLD) PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR ELECTRONICALLY BY ANY THIRD PARTY.

NOTE
THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY, UNLESS SIGNED. FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED. DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION.

IF IN DOUBT - ASK.

PARK LAKE ADARE PTY LTD PO BOX 4107 SPRINGFIELD QLD 4300

PROPOSED SUBDIVISION
174 ADARE ROAD, ADARE, QLD 4343
STAGES 4 AND 5

DRAWING TITLE
BUSHFIRE TRAIL 5 LONGITUDINAL

SCALE 1:500 (HORIZONTAL)


SECTION - SHEET 3


50m


BR242001


SCALE 1:50 (VE	RTICAL)			
DRAWING STATUS			PROVAL OR CONSTRUCT	TON
PROJECT LEADER CK	DESIGNER MP		SIGNATURE	GK.
DRAFTSPERSON MP	AS SHC	NWO	15/04/24	SHEET SIZE A1
IOR No		_	PAWING No	DEVISION


C4711












SUBGRADE SUITABLILTY TO BE CONFIRMED BY SUPERINTENDENT PRIOR TO GRAVEL PLACEMENT


TYPICAL SECTION - BUSHFIRE TRAIL SCALE 1:50



PERMANENT FIRE TRAIL POST DETAIL


FIRE TRAIL NOTES

- 1. FIRE TRAIL TO BE IN ACCORDANCE WITH THE APPROVED REPORT "BUSHFIRE RISK ASSESSMENT & MANAGEMENT PLAN" PREPARED BY BUSHLAND PROTECTION SYSTEMS DATED 20TH APRIL 2022.
- 2. PROVIDE A FIRE TRAIL NUMBER SIGN AT EVERY ENTRANCE TO A FIRE TRAIL.
- 3. COUNCIL WILL ALLOCATE TRAIL NUMBERS AND INSTALL NUMBERING ON POST.



FORMATION OF WATERBAR


NOT TO SCALE



WATER BAR ORIENTATION ON THE TRAIL

NOT TO SCALE

TABLE A									
ROAD GRADE	WATER BAR ORIENTATION	SOIL CLASS A WATER BAR SPACING	SOIL CLASS B WATER BAR SPACING	SOIL CLASS C WATER BAR SPACING	WATER BAR HEIGHT				
UP TO 10%	35°	15 - 20m	10 - 12m (apart)	7 - 10m (apart)	0.3 - 0.4m				
11% TO 15%	25°	8 - 10m	7 - 10m	UNDESIRABLE	0.4 - 0.6m				
15% TO 20%	15°	5 - 8m	CONCRETE	CONCRETE	CONCRETE & OUT-FALL				
21% TO 25%	CONCRETE	CONCRETE	CONCRETE	CONCRETE	CONCRETE & OUT-FALL				
26% TO 30%	CONCRETE	CONCRETE	CONCRETE	CONCRETE	CONCRETE & OUT-FALL				
ABOVE 30% RELOCATE TRAIL ALIGNMENT		RELOCATE TRAIL ALIGNMENT	RELOCATE TRAIL ALIGNMENT	RELOCATE TRAIL ALIGNMENT	RELOCATE TRAIL ALIGNMENT				









	CLIENT
₹ IT	PARK LAKE ADARE PTY LTD
	PO BOX 4107 SPRINGFIELD QLD 4300

PROJECT TITLE
PROPOSED SUBDIVISION
174 ADARE ROAD, ADARE, QLD 4343
STAGES 4 AND 5

BUSHFIRE '

ED SUBDIVISION AD, ADARE, QLD 4343	FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION					
5	PROJECT LEADER CK	DESIGNER MP	SIGNATURE	GK.		
TRAIL DETAILS	DRAFTSPERSON MP	AS SHOWN	15/04/24	SHEET SIZE A1		
ITAIL DLIAILO	JOB No. BR24200		C4716	REVISION		

SCALE 1:50